


CR-184003

TWR-50012



Final Report for the M-52 Spray Booth Qualification Test

July 1990

Prepared for:

NATIONAL AERONAUTICS AND SPACE ADMINISTRATION
GEORGE C. MARSHALL SPACE FLIGHT CENTER
MARSHALL SPACE FLIGHT CENTER, ALABAMA 35812

Contract No. NAS8-30490
DR No. 5-3
WBS No. 4B102-10-07
ECS No. SS3456

Thiokol CORPORATION
SPACE OPERATIONS

P.O. Box 707, Brigham City, UT 84302-0707 (801) 863-3511

Publications No. 91073


(NASA-CR-184003) M-52 SPRAY BOOTH
QUALIFICATION TEST Final Report (Thiokol
Corp.) 370 p

NOO-27727

CSCL 14th

Unclassified
0297564

63/09



Final Report for the M-52 Spray Booth Qualification Test

Prepared by:




Test Planning and Reports
Systems Engineer

Approved by:



Requirements Manager



7-17-90


Design Engineer




Program Manager



Systems Integration Engineer



System Safety



Reliability



P.C. Tydeck 7-18-90

Data Management/Release
ECS No. SS3456

ABSTRACT

This report documents the procedures, performance, and results obtained from the M-52 spray booth qualification test. The test was conducted at Thiokol Corporation, Space Operations, M-52 Inert Parts Preparation facility. The purpose of this testing sequence was to ensure the spray booth would produce flight qualified hardware.

The testing sequence was conducted in two series. The first series was conducted under CTP-0142, Revision A. The second series was conducted in accordance with CTP-0142, Revision B.

The test sequence started with CTP-0142, Revision A. The series consisted of the contamination removal test and the performance test. The contamination removal test was used to assess the Teflon level in the spray booth. The performance test consisted painting and Chemloking a forward dome inside the spray booth per flight procedures. During the performance test, two sets of witness panels (case/insulation and steel/epoxy/steel) were prepared and pull tested.

The CTP-0142, Revision B, series of testing consisted of re-testing the steel\epoxy\steel witness panels. The pull tests analysis indicates the results of the tensile tests were comparable to the systems tunnel witness panel database. The exposed panel set and the control panel set average tensile values were above the A-basis lower limits established on the systems tunnel witness panel database.

It is recommended that the M-52 spray booth be qualified for producing flight hardware.

CONTENTS

<u>Section</u>		<u>Page</u>
1	INTRODUCTION	1
	1.1 Test Article Description	3
2	OBJECTIVES	5
3	EXECUTIVE SUMMARY	7
	3.1 SUMMARY	7
	3.2 CONCLUSIONS	8
	3.3 RECOMMENDATIONS	8
4	INSTRUMENTATION	9
5	PHOTOGRAPHY	9
6	RESULTS AND DISCUSSION	11
	6.1 TEST ARTICLE ASSEMBLY	11
	6.2 TEST DESCRIPTION	11
	6.2.1 CTP-0142, Revision A, Testing Services	11
	6.2.2 CTP-0142, Revision B, Testing Services	20
7	APPLICABLE DOCUMENTS	31

Appendices

<u>Appendix</u>		<u>Page</u>
A	Preliminary FTIR Sample Wipes	A-1
B	Second FTIR Sample Wipes	B-1
C	Third FTIR Sample Wipes	C-1
D	Fourth FTIR Sample Wipes	D-1
E	Process Modification Discussion	E-1
F	Fifth FTIR Sample Wipes	F-1
G	Sixth FTIR Sample Wipes	G-1
H	Final FTIR Sample Wipes	H-1
I	Environmental Fallout Panels FTIR Results	I-1
J	NVR/Particle Counter Results	J-1
K	NASA Test Box Results/FTIR Scans	K-1
L	Witness Panel Pull Test Data	L-1
M	Engineering Evaluation Results	M-1
N	CTP-0142, Revision A, Conscan Data	N-1
O	Postperformance Fallout Panel FTIR Data	O-1
P	CTP-0142, Revision B, Conscan Data	P-1
Q	CTP-0142, Revision B, Witness Panel Pull Test Data	Q-1
R	Pass/Fail Criteria	R-1

FIGURES

<u>Figure</u>		<u>Page</u>
1	Spray Booth Configuration	4
2	Spray Booth East Wall (before cleaning)	12
3	FTIR Wipe Locations	13
4	East Wall After First Cleaning	14
5	Contamination Removal Test Setup	16
6	Performance Test Setup	18
7	Degreased Witness Panels ("A" through "E")	21
8	Degreased Witness Panels ("F" through "J")	22
9	Conscan Process	23
10	Before Operational Cycle	24
11	Witness Panels (postcure, prepull)	26
12	Witness Panel "E" (postpull)	27
13	Witness Panel "J" (postpull)	28
14	Witness Panel Database Graph	29

ABBREVIATIONS AND ACRONYMS

μ	microns
deg	degree
ft	foot
ft ²	square foot
ft ³	cubic foot
FTIR	Fourier transform infrared (spectroscopy)
hr	hour
mg	milligram
NA	not applicable
NASA	National Aeronautics and Space Administration
NVR	nonvolatile residue
pli	pounds per linear inch
psi	pounds per square inch
R&D	research and development
RSRM	redesigned solid rocket motor
TRR	test readiness review

INTRODUCTION

This report documents the procedures, performance, and results obtained from the M-52 spray booth qualification test. The test was conducted at Thiokol Corporation, Space Operations, M-52 Inert Parts Preparation facility. The purpose of this testing sequence was to ensure the spray booth would produce flight qualified hardware.

The testing sequence was conducted in two series. The first series was conducted under CTP-0142, Revision A. The second series was conducted in accordance with CTP-0142, Revision B. The second series was conducted due to the failure of the epoxy/steel/epoxy witness panels to meet the pass/fail criteria. The pass/fail criteria taken from TWR-60445 is:

- a. Detectable Teflon shall constitute a test failure. There must be no detectable Teflon as verified by Fourier transform infrared (FTIR) (spectroscopy) analysis of the surface wipes, environmental fallout panels, and the NASA Test Box filter. No atypical levels of nonvolatile residue (NVR), as verified by NVR analysis of surface wipes and environmental fallout panels (compared to nominal paint pit conditions) are acceptable.
- b. Inability to perform flight process shall constitute a test failure. Demonstrate that paint/Chemlok® process can be performed on flight hardware inside the spray booth.
- c. Processed hardware must meet established standards. Compare witness panel bond strength data to existing witness panel statistical database. Cross-hatch paint adhesion tests must be within developed redesigned solid rocket motor (RSRM) witness panel data history.

The steel/epoxy/steel bond strength configuration was used because it was more sensitive to contaminants. An engineering assessment indicated that the pull test results were outside the established tolerance of three standard deviations. This assessment violated pass/fail Criteria C.

The design team re-evaluated the testing sequence. The result of this evaluation was Revision B to CTP-0142. The revision addressed only the steel/epoxy/steel witness panels. The pass/fail criteria was rewritten into the test readiness review (TRR) package as follows:

a. Contamination Removal Test

1. Teflon – No indications from FTIR analysis on booth wipes or environmental fallout panels.
2. NVR – Amount of NVR is below the accurately detectable limit of 2 mg/ft². Therefore, pass/fail criteria is not applicable (NA).
3. Particulate – ≤ 1,000 particle/ft³ for particles of 5 μ or greater.

b. Performance Test

1. Vulcanized bonds – Within 3 σ (> X -3σ) of witness panel database.
2. Steel-epoxy bonds – If the exposed panel set (five total) has significantly less bond strength at the 95 percent confidence level than the control panel set (five total), then the test has failed.

Pass/fail Criteria 2.B was the only criteria that CTP-0142, Revision B addressed. After the test was repeated, it was discovered the statistical pass/fail criteria was not met because the discriminatory capability of the test was underestimated.

Pass/fail Criteria 2.B was revised as follows (Appendix R):

Pass: If the exposed panels averages are above the systems tunnel witness panel database A-basis lower limit, or if the exposed panel set does not have a significantly lower tensile adhesion bond strength than the control panels at the 95 percent confidence level.

Fail: If any of the exposed panel averages fall below the systems tunnel witness panel database A-basis lower limit, and the exposed panel set has a significantly lower tensile adhesion bond strength than the control panels at the 95 percent confidence level.

The witness panel data that was produced by CTP-0142, Revision B, did meet the revised pass/fail criteria.

1.1 TEST ARTICLE DESCRIPTION

The test article consisted of a stainless steel room, 21 ft wide by 36 ft long with an 11 ft high ceiling. The south wall provided a full wall filter vapor exhaust system. The floor had been encapsulated prior to testing. The spray booth had two doors on the west wall for personnel access, and one large door on the north wall used for items to be painted (Figure 1).





Figure 1. Spray Booth Configuration

A028512a

OBJECTIVES

The objectives are taken from Test Plan CTP-0142, Revision B.

- a. Verify the M-52 Spray Booth is free of Teflon and all other contamination.
- b. Certify the M-52 Spray Booth for painting flight components.
- c. Certify that the M-52 Spray Booth contamination/cleanliness level is both adequate for spraying paint and/or adhesives and the contamination/cleanliness controls placed on the booth will provide the stability required for processing flight hardware through a "critical process".



EXECUTIVE SUMMARY

3.1 SUMMARY

The testing sequence was conducted in two series. The first series was conducted under CTP-0142, Revision A. The second series was conducted in accordance with CTP-0142, Revision B.

The test sequence started with CTP-0142, Revision A. The series consisted of the contamination removal test and the performance test. The contamination removal test was used to assess the Teflon level in the spray booth. The performance test consisted painting and Chemloking a forward dome inside the spray booth per flight procedures.

FTIR samples, environmental fallout panels, a NASA test box filter, particulate counts, and NVR data were analyzed during the contamination removal test for the presence of Teflon and found to be acceptable.

The painting/Chemloking procedures were performed on a forward dome inside the spray booth without incident and were found to be acceptable. During the performance test, two sets of witness panels were prepared and pull tested. One set was prepared for case/insulation bond strength testing and one set was prepared for steel/epoxy/steel bond strength testing. The case/insulation witness panels used in CTP-0142, Revision A, had acceptable bond strengths. The steel/epoxy/steel witness panels had predominately adhesive failure and an average bond strength that was not within five standard deviations of the established steel/epoxy/steel witness panel database.

The CTP-0142, Revision B, series of testing consisted of re-testing the steel\epoxy\steel witness panels. A total of ten panels were prepared and tested. The pull tests analysis indicates the results of the tensile tests were comparable to the systems tunnel witness panel database. The exposed panel set and the control panel set average tensile values were above the A-basis lower limits established on the systems tunnel witness panel database.

3.2 CONCLUSIONS

- | <u>Objective</u> | <u>Conclusion</u> |
|---|--|
| a. Verify the M-52 spray booth is free of Teflon and all other contamination. | Verified. The FTIR wipes proved that the spray booth was free of Teflon contamination. |
| b. Certify the M-52 spray booth for painting flight components. | Certified. During the performance portion of the test, a forward dome was moved into the spray booth and processed (primer and top coat sprayed on the outer diameter, Chemlok primer and bonding agent sprayed on the inner diameter) per flight procedures without incident. |
| c. Certify that the M-52 Spray Booth contamination/cleanliness level is both adequate for spraying paint and/or adhesives and the contamination/cleanliness controls placed on the booth will provide the stability required for processing flight hardware through a "critical process". | Certified. The contamination levels in the spray booth are comparable with the bonding facility already in use. The witness panel data per CTP-0142, Revision B, proved the cleanliness of the spray booth. |

3.3 RECOMMENDATIONS

It is recommended that the M-52 spray booth be qualified for producing flight hardware.

INSTRUMENTATION


The following instruments/measuring devices were used to validate the test:

- a. Conscan II unit
- b. Atcor Portable Particulate Counter
- c. Instron Tensile Machine
- d. Analog Diffuse Reflectance FTIR
- e. Grant Series Squirrel Meter/Logger
- f. NASA Test Box

Calibration system requirements were in accordance with MIL-STD-45662.

PHOTOGRAPHY

Still black and white and color photographs of the test article configuration were taken. Copies of the photographs (series Numbers 116023, 116282, 117017, 117716, 117672, and 117654) are available from the Thiokol Corporation Photographic Services department.



RESULTS AND DISCUSSION

6.1 TEST ARTICLE ASSEMBLY

The spray booth did not need assembly. The case/insulation witness panels, the epoxy/steel/epoxy witness panels, and the environmental fallout panels were assembled and prepared according to TWR-17123 for the first test series in CTP-0142, Revision A. The epoxy/steel/epoxy witness panels were assembled and prepared according to CTP-0142, Revision B, for the second test series.

6.2 TEST DESCRIPTION

The testing sequence was conducted in two series. The first series was conducted under CTP-0142, Revision A. The second series was conducted in accordance with CTP-0142, Revision B.

6.2.1 CTP-0142, Revision A, Testing Series

The test sequence started with CTP-0142, Revision A. The series consisted of the contamination removal test (Figure 2) and the performance test. The results of these tests are described as follows.

6.2.1.1 Contamination Removal Test Results. The contamination removal test was used to assess the Teflon level in the spray booth. FTIR samples, environmental fallout panels, a NASA Test Box filter, particulate counts, and NVR data were analyzed in this assessment.

6.2.1.1.1 FTIR Sample Analysis. The FTIR analysis of the spray booth walls and ceiling is described in this section. Prior to any testing, the spray booth was cleaned and FTIR wipes were taken from the walls and ceiling. There were 21 samples analyzed. The areas where the wipes were taken are defined in Figure 3. The results of the wipes showed Teflon present in the spray booth (Appendix A).

After the spray booth was cleaned per CTP-0142, Revision A (Figure 4), a second FTIR wipe was conducted. There were 26 samples analyzed. The results of the wipes showed Teflon present in the spray booth (Appendix B).

ORIGINAL PAGE
BLACK AND WHITE PHOTOGRAPH

N1160233-2




Figure 2. Spray Booth East Wall (before cleaning)

REVISION _____

DOC NO. TWR-50012 VOL _____
SEC PAGE

ORIGINAL PAGE IS
OF POOR QUALITY







Figure 3. FTIR Wipe Locations

A028513a

ORIGINAL PAGE
BLACK AND WHITE PHOTOGRAPH

N116282-4




Figure 4. East Wall After First Cleaning

The spray booth was cleaned a second time per CTP-0142, Revision A. A third FTIR wipe was conducted. There were 26 samples analyzed. The results of the wipes showed Teflon present in the spray booth (Appendix C).

Before a third cleaning was done, a fourth FTIR wipe was conducted on the spray booth north door, inside the air ducts in the spray booth ceiling, on the outside blower housing, on the outside blower blades on the spray booth roof, on the outside roof by the blower ducts, on the outside screen of the blower, and on an east wall area that was suspected as having Teflon embedded in/on its surface (Appendix D). It was discovered that the cleaning aids and solvent were not disposed of frequently (Appendix E). The cleaning process was modified to dispose of the cleaning aids/solvent frequently to prevent movement of Teflon from one area to another.

The spray booth was cleaned a third time and a fifth FTIR wipe was conducted. A total of 26 samples were analyzed (Appendix F). Of the 26 samples, two areas (East Wall No. 2 Low, see Figure 3, and the North Door West Side) were identified as having traces of Teflon, the other 24 showed no signs of Teflon. The two areas were re-cleaned and FTIR wipes were analyzed. The two areas showed no presence of Teflon (Appendix G).

6.2.1.1.2 Environmental Fallout Panel Results. The environmental fallout panels (Figure 5) were analyzed for Teflon and NVR contamination. FTIR wipes were taken from the panels before and after the first and second spray booth operational cycles (5 hr at 135°F). The wipes included panel samples and particulate samples taken from the panels. A total of 32 samples (eight before each 5-hr operational cycle and eight after each 5-hr operational cycle) were analyzed. No Teflon was detected on any of the samples (Appendix I).

NVR contamination analysis was conducted before the spray booth cleaning started and after the spray booth was declared clean of Teflon. The detectable limit of NVR was 2.0 mg/ft². After the spray booth was cleaned, the northwest environmental fallout panel showed 2.2 mg/ft². All of the other environmental fallout panels showed less than 2.0 mg/ft² of NVR levels (Appendix J).

6.2.1.1.3 Particle Counter Results. The particle counter (Figure 5) was used before the first cleaning operation per CTP-0142, Revision A, and after the last cleaning

ORIGINAL PAGE
BLACK AND WHITE PHOTOGRAPH

N118023-5




Figure 5. Contamination Removal Test Setup

operation per CTP-0142, Revision A. The particle counter uses lasers to count particulate in the air. It does not trap particulate in a filter. Therefore, no FTIR or NVR analysis were conducted on the particulate counts. Data from the first particle counter usage was lost. The average particulate count after the last spray booth cleaning was 14 particles (5μ or larger)/ft³ of air (Appendix J). The pass/fail criteria was established at less than or equal to 1,000 particles/ft³ for particles of 5μ or larger. The particulate count was well within the pass/fail criteria.

6.2.1.1.4 NASA Test Box Results. The NASA Test Box (Figure 5) was used to catch airborne particles for FTIR analysis. The Test Box was used before the first spray booth cleaning per CTP-0142, Revision A, and after the last spray booth cleaning. The FTIR analysis showed no Teflon detected on the Test Box filter (Appendix K).

6.2.1.2 Performance Test Results. The performance test consisted of painting and Chemlocking a forward dome inside the spray booth per flight procedures. Two sets of witness panels (Figure 6) were prepared per TWR-17123. One set was prepared for case/insulation bond strength testing and one set was prepared for steel/epoxy/steel bond strength testing.

6.2.1.2.1 Witness Panel Results. The case/insulation witness panels (three total) showed average tensile adhesion strengths of 823 psi, 822 psi, and 858 psi. The average peel strengths for the case/insulation witness panels were 179 pli, 162 pli, and 166 pli. The cases/insulation witness panel database mean is 756 psi and 172 pli. The case/insulation witness panels used in CTP-0142, Revision A, had acceptable bond strengths (Appendix L).

The steel/epoxy/steel witness panels did not fare as well. To begin with, only two panels were prepared. CTP-0142, Revision A, required three panels to be tested. The steel/epoxy steel witness panels had average tensile strengths of 2,914 psi and 3,875 psi (Appendix L). The steel/epoxy/steel witness panel database mean is 5,588 psi and that mean at five standard deviations is 3,734 psi. The two steel/epoxy/steel witness panels had predominately adhesive failure and an average bond strength that was not within five standard deviations of the established steel/epoxy/steel witness panel database.

ORIGINAL PAGE
BLACK AND WHITE PHOTOGRAPH

N117017-1




Figure 6. Performance Test Setup

An investigation revealed the following deviations concerning the steel/epoxy/steel bond strength configuration witness panels:

- a. The witness panels were not prepared in accordance with Section 8.2.2, subsection A of the test plan. The panels were prepared without silane primer application to the steel bond surface. Silane primer is an adhesion promoter that increases the nominal bond strength approximately 10 percent and precludes possible surface contamination.
- b. The environment of the test panels was not adequately controlled prior to epoxy and test button application. The witness panels remained in the spray booth after the forward dome was coated without any contamination controls for approximately 7 days before being sent to the R&D Lab for test assembly.
- c. While on the panel holder, the witness panels were covered with 'black poly' plastic covering after the forward dome was coated and prior to epoxy and test button application. The witness panel bond strengths could have adversely affected by transference of contamination from 'black poly' plastic covering.

The results of the steel/epoxy/steel witness panel tests initiated an engineering evaluation test. This test was performed outside the parameters of CTP-0142, Revision A. The test objective was to account for the effects of the test variables introduced during the test performance. The testing sequence and test conclusions are outlined in Appendix M. The analysis of the engineering evaluation initiated CTP-0142, Revision B.

6.2.1.2.2 Dome Procedure Analysis. The performance test consisted of painting (primer and topcoat) and Chemloking (primer and bonding agent) a forward dome (see Figure 6) inside the spray booth per flight procedures. The procedures were performed without incident and were found to be acceptable.

In addition to the painting sequence, Ron Brock, NASA, requested that witness panels be paint adhesion tested. Three witness panels were placed inside the spray booth and painted along with the test dome. Two witness panels were placed in the paint pit and painted with the Flight 17B aft dome. All five panels were then tested per ASTM-D-3359-87, Method B. The panels were all rated '4B'. The paint results can vary from '0B' (worst case) to '5B' (perfect). The '4B' rating is most common for flight component witness panels.

6.2.1.2.3 Conscan Analysis. The test dome was conscanned before the Chemloking process was accomplished. A total of 32 points on the interior of the test dome were conscanned. An acceptable reading had to be above 378. All 32 readings were above 378 (Appendix N).

6.2.1.2.4 Contamination Removal Analysis. After the performance test was conducted, 28 wipes were taken from the walls and ceiling and FTIR analyzed. The analysis showed no Teflon present in the spray booth (Appendix H). The environmental fallout panels were analyzed for the presence of Teflon and NVR contamination. The analysis showed no presence of Teflon (Appendix J and O). The particulate count was 24 particles (5μ or larger)/ft³ of air (Appendix J).

6.2.2 CTP-0142, Revision B, Testing Series

This series of testing consisted of re-testing the steel\epoxy\steel witness panels. A total of ten panels (Figures 7 and 8) were prepared and tested per CTP-0142, Revision B.

The steel\epoxy\steel witness panels were grit blasted with new zirconium silicate grit and vapor degreased with methyl chloroform. After the vapor degrease, the witness panels were conscanned (Figure 9). A reading above 433 was acceptable. Each panel was conscanned five times. The lowest reading average was 756. The panels were acceptable after the conscan (Appendix P).

The witness panels were identified "A" through "J". "A" through "E" were designated as the test set of panels and "F" through "J" were designated as the control set of panels. The panels were wrapped in craft paper and placed in the spray booth (Figure 10).

The craft paper was removed from the test set of panels. The spray booth was subjected to an operational cycle (5 hr at 135°F). After the operational cycle, the test set of panels was re-wrapped in craft paper and shipped to the development laboratory.

A total of 120 tensile buttons were prepared with silane primer and dried for 3 hr. On each witness panel, a 24-hole template and 12 bondline spacers (0.03 in.) were installed. EA 934NA epoxy was applied into each locating hole with a bondline spacer. A thin layer of the epoxy was applied to each tensile button to wet the bond surface. The tensile buttons were assembled to the corresponding locator holes

Thiokol CORPORATION
SPACE OPERATIONS

ORIGINAL PAGE
BLACK AND WHITE PHOTOGRAPH

N117654-1



Figure 7. Degreased Witness Panels ("A" through "E")

REVISION _____

DOC NO. TWR-50012 VOL
SEC PAGE

Thiokol CORPORATION
SPACE OPERATIONS

ORIGINAL PAGE
BLACK AND WHITE PHOTOGRAPH

N117654-2



Figure 8. Degreased Witness Panels ('F' through 'J')



N117854

Figure 9. Conscan Process

Thiokol CORPORATION
SPACE OPERATIONS

ORIGINAL PAGE
BLACK AND WHITE PHOTOGRAPH

N117654-5




Figure 10. Before Operational Cycle

REVISION _____

ORIGINAL PAGE IS
OF POOR QUALITY

DOC NO. TWR-50012 VOL _____
SEC PAGE

with bondline spacers and epoxy. The witness panels were installed into pressure holders and allowed to cure for a minimum of 36 hr at ambient temperature (Figure 11).

The pull tests were conducted by the Contamination Control Laboratory (Figures 12 and 13). The pull tests analysis indicates the results of the tensile tests (Appendix Q) are comparable to the systems tunnel witness panel database. The exposed panel set and the control panel set average tensile values were above the A-basis lower limits established on the systems tunnel witness panel database (Figure 14). The statistical pass/fail criteria was not met because the discriminatory capability of the test was underestimated.

ORIGINAL PAGE
BLACK AND WHITE PHOTOGRAPH

N117672-1





Figure 11. Witness Panels (postcure, prepull)

Thiokol CORPORATION
SPACE OPERATIONS

ORIGINAL PAGE
BLACK AND WHITE PHOTOGRAPH

N117716-9



REVISION _____

DOC NO. TWR-50012 | VOL
SEC PAGE

Figure 12. Witness Panel 'E' (postpull)

Thiokol CORPORATION
SPACE OPERATIONS

ORIGINAL PAGE
BLACK AND WHITE PHOTOGRAPH

N117716-8





Figure 13. Witness Panel 'J' (postpull)

REVISION


DOC NO. TWR-50012 VOL
SEC PAGE

RSRM Systems Tunnel Witness Panels
Type III (IIC Panels) <Steel/Epoxy/Steel>
With A-basis lower limit




A028514a

Figure 14. Witness Panel Database Graph



APPLICABLE DOCUMENTS

<u>Number</u>	<u>Title</u>
MIL-STD-45662	Calibration System Requirements
TWR-17123	RSRM Space Shuttle Witness Panel Implementation Plan Case/Insulation/Liner/Propellant Weather Seal and Sys- tems Tunnel
CTP-0142A	Qualification Test Plan for the M-52 Spray Booth
CTP-0142B	Qualification Test Plan for the M-52 Spray Booth
TWR-60445	Quick Look Report for the M-52 Spray Booth Qualification under CTP-0142, Revision A
ASTM-D-3359	Standard Test Methods for Measuring Adhesion by Tape Test



Appendix A

Preliminary FTIR Sample Wipes

REVISION _____

91073-2.1

DOC NO. TWR-50012 | VOL _____
SEC | PAGE _____
A-1

LABORATORY REPORT

21 Mar. 1990

Originator: Vern Fitch
Ext 6344, M/S L62B

Request: LWR 592584
Laboratory log # 02-21-90-31122

Subject: FTIR Analysis of M-52 Spray Booth Wipe Samples for Teflon
Decontamination Testing, CTP-0142-A

FTIR analysis has been carried out on wipe samples taken from the ceiling and walls of the M-52 spray booth. The samples up to the third cleaning were taken by wiping an area about 5" x 5" square with a polypropylene wipe wet with Freon TF. The samples taken after the third cleaning and those from the surfaces outside the booth were obtained by wiping an area approximately 2 feet by 1 foot with a methylchloroform wet wipe. The presence of Teflon was detected by the appearance of the C-F absorbance peaks at about 1160 and about 1230 wavenumbers.

Sample Location	Occurrence of Teflon After Cleaning				
	Before	First	Second	Third	Fourth
South Wall #1 (High) (East)	Present	Present	None	---	None
South Wall #1 (Low) (East)	---	---	---	None*	---
South Wall #2 (High) (West)	Present	Trace	None	---	None
South Wall #2 (Low) (West)	---	---	---	None*	---
North Door East Side	---	---	---	Present*	None
North Door West Side	---	---	---	Present*	Trace**
East Ceiling #1 (North)	Trace	Present	None	---	None
East Ceiling #2	Trace	Present	None	---	---
East Ceiling #3	None	Trace	None	---	None

TWR-50012

<u>Sample Location</u>	Occurrence of Teflon After Cleaning				
	<u>Before</u>	<u>First</u>	<u>Second</u>	<u>Third</u>	<u>Fourth</u>
East Ceiling #4 (South)	Present	Present	Trace	---	None
West Ceiling #1 (North)	None	None	None	---	None
West Ceiling #2	Trace	None	Trace	---	None
West Ceiling #3	Trace	None	None	---	---
West Ceiling #4 (South)	None	None	None	---	None
East Wall #1 (High) (North)	Present	None	Trace	---	None
East Wall #1 (Low) (North)	Trace	Trace	Trace	None	None
East Wall #2 (High)	Present	Present	Trace	---	None
East Wall #2 (Low)	Present	Trace	Present	Trace	Trace**
East Wall #3 (High)	Present	Present	Present	---	None
East Wall #3 (Low)	Present	Present	Trace	---	None
East Wall #4 (High) (South)	Present	Present	Trace	---	None
East Wall #4 (Low) (South)	Present	Trace	Trace	None	None
West Wall #1 (High) (North)	Trace	Trace	Trace	---	None
West Wall #1 (Low) (North)	None	Trace	Trace	None	None
West Wall #2 (High)	None	Trace	None	---	None
West Wall #2 (Low)	---	None	None	---	None
West Wall #3 (High)	---	None	Trace	---	None
West Wall #3 (Low)	---	Present	Trace	Trace	None
West Wall #4 (High) (South)	---	Present	None	---	None
West Wall #4 (Low)	Trace	Present	Trace	None	None

* The low south wall and north door samples were only taken after the 3rd cleaning.

** These areas were cleaned a fifth time. No Teflon was detected after the fifth cleaning.

In addition to the above test locations, an embedded surface on the east wall was sampled before and after sanding with the following results:


<u>Sample Location</u>	<u>Occurrence of Teflon</u>
East Wall Embedded Surface	
Before Sanding	Trace
After First Sanding	Trace (less than before sanding)
After Second Sanding	None

Also, a number of samples were taken outside of the spray booth with the following results:

<u>Sample Location</u>	<u>Occurrence of Teflon</u>
Spray Booth Ceiling Inside Air Ducts #1	None
Spray Booth Ceiling Inside Air Ducts #2	None
Outside Blower Housing	None
Outside Blower Blades on Roof	None
Outside Roof by Blower Blades to Spray Booth	None
Outside Screen of Blower	None
Control Sample #1	None
Control Sample #2	None
Control Sample #3	None

Copies of the FTIR spectra are attached.



R. C. Raisor, Spectrochemical Analysis
LAB90061
B1222



TWR-50012


A-5

M-52 SPRAY BOOTH EAST WALL #1 HIGH, ATR, BEFORE CLEAN, 592584.105
01 Mar 90 08:48:34




TWR-50012

A-6




TWR-50012

A-7



TWR-50012


A-8



TWR-50012


A-9

M-52 BOOTH, EAST WALL #3 LOW, BEFORE CLEANING, LWR 592584.102
28 Feb 90 13:31:21



TWR-50012


A-10



TWR-50012


A-11

M-52 BOOTH, EAST WALL #4 HIGH, BEFORE CLEANING, 592584.101 28 Feb 90 13:06:09



TWR-50012


A-12



TWR-50012


A-13

M-52 SPRAY BOOTH WEST WALL #1 HIGH, ATR, BEFORE CLEAN, 592584.111 01 Mar 90 10:58:33



TWR-50012


A-14



TWR-50012


A-15

M-52 SPRAY BOOTH SOUTH WALL #1 HIGH, ATR, BEFORE CLEAN, 592584.113 01 Mar 90 11:25:00



TWR-50012


A-16



TWR-50012


A-17

M-52 SPRAY BOOTH EAST CEILING #1, ATR, BEFORE CLEAN, 592584. 120 01 Mar 90 14:02:03



TWR-50012


A-18



TWR-50012


A-19

M-52 SPRAY BOOTH EAST CEILING #3, ATR, BEFORE CLEAN, 592584. 122 01 Mar 90 14:49:31



TWR-50012


A-20



TWR-50012


A-21

M-52 SPRAY BOOTH WEST CEILING #4, ATR, BEFORE CLEAN, 592584.116 01 Mar 90 13:09:07




TWR-50012

A-22




M-52 SPRAY BOOTH WEST CEILING #2, ATR, BEFORE CLEAN, 592584.119 01 Mar 90 13:54:34




TWR-50012

A-24



TWR-50012


A-25



Appendix B
Second FTIR Sample Wipes


REVISION _____

DOC NO. TWR-50012 VOL _____
SEC PAGE B-1




TWR-50012

B-2




TWR-50012

B-3



TWR-50012
B-4




TWR-50012

B-5


M-52 SPRAY BOOTH EAST WALL #2 HIGH, ATR, AFT. CLEAN, 592584.005

27 Feb 90 09:39:53



TWR-50012


B-6




TWR-50012

B-7

M-52 SPRAY BOOTH EAST WALL #3 HIGH, ATR, AFT. CLEAN, 592584.007 27 Feb 90 09:57:29




TWR-50012
B-8




TWR-50012

B-9




TWR-50012
B-10




TWR-50012

B-11




TWR-50012
B-12



TWR-50012


B-13

M-52 SPRAY BOOTH WEST WALL #2 HIGH, ATR, AFT, CLEAN, 592584.013 27 Feb 90 11:26:04



TWR-50012


B-14



TWR-50012


B-15

M-52 SPRAY BOOTH WEST WALL #3 HIGH, ATR, AFT CLEAN, 592584.015 27 Feb 90 13:11:17




TWR-50012

B-16




TWR-50012

B-17



TWR-50012


B-18



TWR-50012


B-19

M-52 SPRAY BOOTH EAST CEILING #1, ATR, AFT CLEAN, 592584.019 27 Feb 90 14:08:55



TWR-50012


B-20



TWR-50012


B-21

M-52 SPRAY BOOTH EAST CEILING #3, ATR, AFT. CLEAN, 592584.021 27 Feb 90 14:47:51




TWR-50012

B-22




TWR-50012
B-23

M-52 SPRAY BOOTH WEST CEILING #1, ATR, AFT. CLEAN, 592584. 023
28 Feb 90 08:30:29




TWR-50012

B-24




TWR-50012

B-25



TWR-50012

B-26



TWR-50012

B-27




Appendix C

Third FTIR Sample Wipes

REVISION _____


DOC NO. TWR-50012 VOL _____
SEC _____ PAGE _____
C-1

M-52 SPRAY BOOTH, EAST WALL #1 HIGH, 2ND CLEAN, ATR, 592584.2011 05 Mar 90 11:15:05



TWR-50012


C-2



TWR-50012

C-3

M-52 SPRAY BOOTH, EAST WALL #2 HIGH, 2ND CLEAN, ATR, 592584.203 05 Mar 90 13:26:45




TWR-50012

C-4

M-52 SPRAY BOOTH, EAST WALL #2 LOW, 2ND CLEAN, ATR, 592584. 204


05 Mar 90 13:38:16




TWR-50012

C-5

M-52 SPRAY BOOTH, EAST WALL #3 HIGH, 2ND CLEAN, ATR, 592584.205 05 Mar 90 13:47:34




TWR-50012
C-6



TWR-50012

C-7


M-52 SPRAY BOOTH, EAST WALL #4 HIGH, 2ND CLEAN, ATR, 592584.207 05 Mar 90 14:35:26



TWR-50012
C-8


M-52 SPRAY BOOTH, EAST WALL #4 LOW, 2ND CLEAN, ATR, 592584. 208

05 Mar 90 14:44:35




TWR-50012

C-9



TWR-50012
C-10




TWR-50012


C-11

C-2

M-52 SPRAY BOOTH, WEST WALL #2 HIGH, 2ND CLEAN, ATR, 592584. 211 06 Mar 90 07:51:31




TWR-50012
C-12



TWR-50012


C-13

M-52 SPRAY BOOTH, WEST WALL #3 HIGH, 2ND CLEAN, ATR, 592584.213 06 Mar 90 08:15:17




TWR-50012

C-14



TWR-50012
C-15

M-52 SPRAY BOOTH, WEST WALL #4 HIGH, 2ND CLEAN, ATR, 592584.215 06 Mar 90 08:35:28




TWR-50012

C-16

M-52 SPRAY BOOTH, WEST WALL #4 LOW, 2ND CLEAN, ATR, 592584.216


06 Mar 90 08:52:29




TWR-50012

C-17

M-52 SPRAY BOOTH, SOUTH WALL #1, 2ND CLEAN, ATR, 592584.217 06 Mar 90 09:00:41




TWR-50012
C-18




TWR-50012

C-19

M-52 SPRAY BOOTH, EAST CEILING #1, 2ND CLEANING, ATR, 592584.219 06 Mar 90 10:00:59




TWR-50012
C-20




TWR-50012

C-21


M-52 SPRAY BOOTH, EAST CEILING #3, 2ND CLEANING, ATR, 592584. 221
06 Mar 90 10:35:24



M-52 SPRAY BOOTH, EAST CEILING #4, 2ND CLEANING, ATR, 592584, 222 06 Mar 90 10:44:12




M-52 SRRAY BOOTH, WEST CEILING #1, 2ND CLEANING, ATR, 592584.223 06 Mar 90 10:56:14



TWR-50012
C-24


M-52 SPRAY BOOTH, WEST CEILING #2, 2ND CLEANING, ATR, 592584.224 06 Mar 90 11:18:52




TWR-50012

C-25

M-52 SPRAY BOOTH, WEST CEILING #3, 2ND CLEANING, ATR, 592584.025 06 Mar 90 11:29:13




TWR-50012
C-26



TWR-50012

C-27




Appendix D


Fourth FTIR Sample Wipes

REVISION _____


DOC NO. **TWR-50012** | VOL _____
SEC | PAGE _____
D-1



TWR-50012
D-2





TWR-50012
D-3




TWR-50012
D-4

M-52 SPRAY BOOTH, EAST WALL #1 LOW, ATR CLAMP, 592584. 304
13 Mar 90 14:02:13






TWR-50012
D-6




TWR-50012

D-7

M-52 SPRAY BOOTH, WEST WALL #3 LOW, ATR CLAMPED, LWR 592584.308 14 Mar 90 08:46:59



TWR-50012
D-8




TWR-50012


D-9

M-52 SPRAY BOOTH, WEST WALL #4 LOW, ATR CLAMPED, LWR 592584, 309

14 Mar 90 09:02:48




TWR-50012
D-10



TWR-50012


D-11

EAST WALL EMBEDDED AREA AFTER 2ND SANDING, ATR, 592584. 311 14 Mar 90 10:09:45




TWR-50012

D-12




TWR-50012


D-13




TWR-50012
D-14



TWR-50012
D-15




TWR-50012
D-16




TWR-50012

D-17

M-52 SPRAY BOOTH CEILING, INSIDE AIR DUCTS #2, ATR, 592584 316 14 Mar 90 11:28:06




TWR-50012
D-18




TWR-50012

D-19




TWR-50012

D-20



TWR-50012

D-21



TWR-50012
D-22

Appendix E
Process Modification Discussion

REVISION _____

DOC NO. TWR-50012 VOL _____
SEC PAGE E-1

Thiokol CORPORATION
SPACE OPERATIONS

21 March 1990
L623-FY90-M120

TO: Distribution
FROM: V. Fitch
Thermal Insulation Design
SUBJECT: CTP-0142, 'M-52 Spray Booth', Meeting Minutes, 15 March 1990
REFERENCE: L623-FY90-M112, 'Meeting Minutes 3-9-90 CTP-0142 (M-52 Spray Booth), V. Fitch, 9 March 1990

1.0 INTRODUCTION

The second CTP-0142 (M-52 spray booth) meeting was held 15 March. The spray booth is being qualified for paint and Chemlok^R application processes of domes. The spray booth had been previously used for Teflon application processes. The meeting was held to discuss results of FTIR analyses for Teflon^R (not a test plan requirement) directed via the meeting held 9 March in response to cleaning/inspection iterations (See Reference 1).

2.0 SUMMARY

Teflon was detected on the walls and ceiling of the M-52 spray booth subsequent to each of three (1 prior to the test and 2 during the test) labor intensive solvent scrub/rinse cleaning operations. Direction was given to perform the subject FTIR analyses prior to proceeding with the test plan. The subject analyses provided answers to the questions brought forth during the previous meeting. Following completion of the action arrived at via the results of the analyses and dispensed in the subject meeting, direction was given on 20 March to proceed with the test plan (start at paragraph 8.2.1 B) as written.

3.0 CONCLUSIONS

The conclusion arrived at via the results of the subject FTIR analyses are listed below.

- 1) The FTIR analyses were validated as accurate (no false positives).
- 2) Teflon is not present in the spray booth air intake system.
- 3) The Teflon contamination is spotty.

03/23/90 - 10:00 AM - C:\USERS\JDOYLE\DESKTOP\TWR-50012.DOC

A023243a

REVISION _____

DOC NO. TWR-50012 | VOL _____
SEC | PAGE _____
E-2

ORIGINAL PAGE IS
OF POOR QUALITY

- 4) Teflon particles are, in part, embedded within the booth surfaces.
- 5) The cleaning methodology was flawed; contamination was transferred from area to area.

4.0 ACTION

Repeat the cleaning operation. Perform cleaning such that a discrete region (a panel) is scrubbed with solvent soaked scotch-brite pads, scrubbed with detergent and new scotch-brite pads, and then rinsed. Dispose of solvent and cleaning aids and repeat the procedure for each panel. After cleaning the entire booth, perform FTIR analyses for Teflon on the wipes taken over the entire booth. Re-clean any region (not just the randomly selected wipe area within the region) identified as contaminated. Repeat analysis for Teflon by taking another random wipe within the region.

5.0 DISCUSSION

Results of the subject analyses are discussed in sequence with the conclusions.

- 1) Some FTIR results were suspected as being false positives due to background. The suspicion arose from Teflon traces being identified on the new section of the west wall. Analyses for Teflon were performed on three wipes taken on the west wall (recently constructed) outside of the spray booth around the environmental monitor and also on a solvent dampened wipe. The analyses identified that false positives were not occurring.
- 2) Teflon particles were suspected as becoming airborne due to the ventilation system possibly being contaminated. Analyses of wipes taken on the roof by the air intake (1), within the blower housing (2), on the blower fan blade (1), and on the spray booth duct work (2) did not identify a trace of Teflon.
- 3) The detected levels of Teflon were suspected as being skewed due to the size of each wiped area. The subject wipes were taken on a much larger area (approximately 2 ft²) as compared to approximately 25 in² for previous wipes). The results were compared to results after the second test plan cleaning (see attachment A).

Note that each sample wipe is taken randomly within an approximately 7 x 7 ft region. Therefore, a wipe from an area within a region may have Teflon identified for one test and a second wipe from an area within the same region may not have Teflon identified, and vice-versa. Results of the analyses on the wipes demonstrate that the contaminated areas are localized or patchy. Certification of a Teflon free booth requires that all randomly selected wipes test negative for Teflon.

A023243a

Thiokol CORPORATION
SPACE OPERATIONS

- 4) The Teflon was suspected as being embedded in/on surfaces. A localized area of the east wall having obvious residue (oxide) on the surface was wiped, abraded with emery cloth, wiped, abraded, and wiped again. The FTIR analysis of the wipes identified a trace of Teflon, a lesser trace of Teflon, and finally no detected Teflon, respectively. Teflon was embedded within the visible oxide layer. This layer was removed by the abrasion.
- 5) From the discussions of the previous four sections, the conclusion is formed that the cleaning operation was, in part, moving Teflon from area to area. The cleaning aids and solvent were not disposed of frequently and were, hence, a source of contamination

V. Fitch
V. Fitch

Concurred by:

F. B. Baugh
F. B. Baugh, Supervisor
Thermal Insulation Design

VWF/pn

A023243a

REVISION _____

DOC NO. TWR-50012 | VOL _____
SEC PAGE | E-4

LABORATORY REPORT

08 Mar. 1990

Originator: Vern Fitch
 Ext 6344, M/S L62B

Request: LWR 592584
 Laboratory log # 02-21-90-31122

Subject: FTIR Analysis of M-52 Spray Booth for Teflon
 CTP-0142

FTIR analysis has been carried out on wipe samples taken from the ceiling and walls of the M-52 spray booth. The samples were taken by wiping an area about ~~5" x 5"~~ square with a polypropylene wipe wet with Freon TF. The presence of Teflon was detected by the appearance of the C-F absorbance peaks at about 1160 and about 1230 wavenumbers.

Sample Location	Occurrence of Teflon			
	Before	1st Cleaning	2nd Cleaning	3rd Cleaning
South Wall #1 (High) (East)	Present	Present	None	
South Wall #1 (Low) (East)	—	—	—	None*
South Wall #2 (High) (West)	Present	Trace	None	
South Wall #2 (Low) (West)	—	—	—	None*
North Door East Side	—	—	—	Present*
North Door West Side	—	—	—	Present*
East Ceiling #1 (North)	Trace	Present	None	
East Ceiling #2	Trace	Present	None	
East Ceiling #3	None	Trace	None	
East Ceiling #4 (South)	Present	Present	Trace	

Sample Location	Occurrence of Teflon			
	Before	1st Cleaning	2nd Cleaning	3rd Cleaning
West Ceiling #1 (North)	None	None	None	
West Ceiling #2	Trace	None	Trace	
West Ceiling #3	Trace	None	None	
West Ceiling #4 (South)	None	None	None	
East Wall #1 (High) (North)	Present	None	Trace	
East Wall #1 (Low) (North)	Trace	Trace	Trace	None
East Wall #2 (High)	Present	Present	Trace	
East Wall #2 (Low)	Present	Trace	Present	Trace
East Wall #3 (High)	Present	Present	Present	
East Wall #3 (Low)	Present	Present	Trace	
East Wall #4 (High) (South)	Present	Present	Trace	
East Wall #4 (Low) (South)	Present	Trace	Trace	None
West Wall #1 (High) (North)	Trace	Trace	Trace	
West Wall #1 (Low) (North)	None	Trace	Trace	None
West Wall #2 (High)	None	Trace	None	
West Wall #2 (Low)	—	None	None	
West Wall #3 (High)	—	None	Trace	
West Wall #3 (Low)	—	Present	Trace	Trace
West Wall #4 (High) (South)	—	Present	None	
West Wall #4 (Low)	Trace	Present	Trace	None

* The low south wall and north door samples were only taken after the 3rd cleaning.

In addition to the above test locations, an embedded surface on the east wall was sampled before and after sanding with the following results:

<u>Sample Location</u>	<u>Occurrence of Teflon</u>
East Wall Embedded Surface	
Before Sanding	Trace
After First Sanding	Trace (less than before sanding)
After Second Sanding	None

Also, a number of samples were taken outside of the spray booth with the following results:

<u>Sample Location</u>	<u>Occurrence of Teflon</u>
Spray Booth Ceiling Inside Air Ducts #1	None
Spray Booth Ceiling Inside Air Ducts #2	None
Outside Blower Housing	None
Outside Blower Blades on Roof	None
Outside Roof by Blower Blades to Spray Booth	None
Outside Screen of Blower	None
Control Sample #1	None
Control Sample #2	None
Control Sample #3	None

Copies of the FTIR spectra are attached.



R. C. Raisor, Spectrochemical Analysis
LAB90061
B1222

Distribution	M/S
L. Allred	L72A
*R. Andersen	650
F. Baugh	L62B
*D. Call	692
J. Daines	L61
D. Earl	692
N. Eddy	L62B
*V. Fitch	L62B
S. Foth	811
R. Furrows	L72
*L. Manuel	L71
R. Marsh	E63
S. Mildenhall	L90
B. Nelson	L82
*P. Petty	L82
*R. Raisor	245
C. Whitworth	L90
R. Wilks	L62

* Attendees


Appendix F

Fifth FTIR Sample Wipes

REVISION _____


DOC NO. TWR-50012 VOL _____
SEC _____ PAGE _____
F-1

M-52 SPRAY BOOTH, EAST WALL #1 LOW, ATR CLAMP, LWR 592584.401 18 Mar 90 06:11:55




TWR-50012

F-2




TWR-50012

F-3



TWR-50012


F.4



TWR-50012


F-5

M-52 SPRAY BOOTH, EAST WALL #3 LOW, ATR CLAMP, LWR 592584.405
18 Mar 90 06:49:18




TWR-50012

F-6




TWR-50012

F-7



TWR-50012


F-8



TWR-50012


F-9

M-52 SPRAY BOOTH, NORTH DOOR WEST SIDE, ATR CLAMPED, 592584.409 18 Mar 90 07:32:29



TWR-50012
F-10


M-52 SPRAY BOOTH, NORTH DOOR EAST SIDE, ATR CLAMPED, 592584.410 18 Mar 90 08:15:26



TWR-50012

F-11


M-52 SPRAY BOOTH, EAST CEILING #1, ATR CLAMP, LWR 592584. 111 18 Mar 90 08:30:04



TWR-50012

F-12

M-52 SPRAY BOOTH, EAST CEILING #3, ATR CLAMP, LWR 592584. 412 18 Mar 90 08:50:28




TWR-50012

F-13


M-52 SPRAY BOOTH, EAST CEILING #4, LWR 592584. H₁₃ 18 Mar 90 08:58:36

0.2424 0.2051 0.1677 0.1491 0.1304 0.11864 0.11677 0.11304 Absorbance



TWR-50012


F-14



TWR-50012


F-15

M-52 SPRAY BOOTH, WEST CEILING #2, LWR 592584. 115 18 Mar 90 09:22:52



TWR-50012


F-16




TWR-50012

F-17

M-52 SPRAY BOOTH, WEST WALL #1 LOW, LWR 592584.4117 18 Mar 90 09:39:12




TWR-50012
F-18



TWR-50012

F-19

M-52 SPRAY BOOTH, WEST WALL #2 LOW, LWR 592584. q19
18 Mar 90 10:05:04



TWR-50012
F-20

M-52 SPRAY BOOTH, WEST WALL #2 HIGH, ATR CLAMP, 592584. 120
18 Mar 90 11:15:22

0.1363 0.1532 0.1702 0.1872 0.2042 0.2211 0.2381

Absorbance

3800.0 3400.0 3000.0 2600.0 2200.0 1800.0 1400.0 1000.0 600.00

Wavenumber (cm^{-1})


//

TWR-50012


F-21

1731

M-52 SPRAY BOOTH, WEST WALL #3 LOW, ATR CLAMP, 592584. 421
18 Mar 90 11:25:27




TWR-50012
F-22



TWR-50012


F-23

M-52 SPRAY BOOTH, WEST WALL #4, LWR 592584. 123 18 Mar 90 11:40:43



TWR-50012
F-24


M-52 SPRAY BOOTH, WEST WALL #4 HIGH, LWR 592584. 124 18 Mar 90 11:50:35



TWR-50012


F-25

M-52 SPRAY BOOTH, SOUTH WALL #1, LWR 592584. 125 18 Mar 90 12:37:06




TWR-50012

F-26



TWR-50012

F-27




Appendix G


Sixth FTIR Sample Wipes

REVISION _____

DOC NO. TWR-50012 VOL _____
SEC _____ PAGE _____
G-1




TWR-50012
G-2



TWR-50012

G-3



Appendix H
Final FTIR Sample Wipes

REVISION _____

91073-2.8

DOC NO. TWR-50012 VOL _____
SEC PAGE H-1

*Final Test, After performance of test
with done*

LABORATORY REPORT

16 Apr. 1990

Originator: Vern Fitch
Ext 6344, M/S L62B

Request: LWR 597701
Laboratory log # 04-11-90-32197

Subject: FTIR Analysis of M-52 Spray Booth Wipe Samples for Teflon Contamination

FTIR analysis has been carried out on wipe samples taken from the ceiling and walls of the M-52 spray booth. The samples were taken by wiping an area approximately 2 feet by 1 foot with a methylchloroform wet wipe. The presence of Teflon was detected by the appearance of the C-F absorbance peaks at about 1160 and about 1230 wavenumbers.

No Teflon was detected in any of the samples.

Samples were taken from the following locations:

Sample Locations

South Wall #1 (East)

South Wall #2 (West)

North Door East Side

North Door West Side

East Ceiling #1 (North)

East Ceiling #2

East Ceiling #3

East Ceiling #4
(South)


ORIGINAL PAGE IS
OF POOR QUALITY

Sample Locations


West Ceiling #1 (North)
West Ceiling #2
West Ceiling #3
West Ceiling #4 (South)
East Wall #1 (High) (North)
East Wall #1 (Low) (North)
East Wall #2 (High)
East Wall #2 (Low)
East Wall #3 (High)
East Wall #3 (Low)
East Wall #4 (High) (South)
East Wall #4 (Low) (South)
West Wall #1 (High) (North)
West Wall #1 (Low) (North)
West Wall #2 (High)
West Wall #2 (Low)
West Wall #3 (High)
West Wall #3 (Low)
West Wall #4 (High) (South)
West Wall #4 (Low)

Copies of the FTIR spectra are attached.

R. C. Raisor, Spectrochemical Analysis
LAB90104
B1448




TWR-50012
H-4



TWR-50012


H-5

M-52 SPRAY BOOTH EAST WALL #2 HIGH, ATR CLAMP, LWR 597701.003 11 Apr 90 13 46



TWR-50012


H-6



TWR-50012


ORIGINAL PAGE IS
OF POOR QUALITY

H-7



ORIGINAL PAGE IS
OF POOR QUALITY


TWR-50012
H-8



TWR-50012


H-9

ORIGINAL PAGE IS
OF POOR QUALITY




TWR-50012
H-10

ORIGINAL PAGE IS
OF POOR QUALITY




ORIGINAL PAGE IS
OF POOR QUALITY

TWR-50012
H-11




ORIGINAL PAGE IS
OF POOR QUALITY

TWR-50012
H-12



ORIGINAL PAGE IS
OF POOR QUALITY


TWR-50012
H-13



TWR-50012

H-14

ORIGINAL PAGE
OF POOR QUALITY




TWR-50012

H-15


ORIGINAL PAGE IS
OF POOR QUALITY

M-52 SPRAY BOOTH, WEST WALL #3 HIGH, ATR CLAMP, LWR 597701.013 12 Apr 90 07:38:43



TWR-50012
H-16


ORIGINAL PAGE IS
OF POOR QUALITY



TWR-50012
H-17

ORIGINAL PAGE IS
OF POOR QUALITY


M-52 SPRAY BOOTH, WEST WALL #4 HIGH, ATR CLAMP, LWR 597701 015
12 Apr 90 08:23:24
0 1602
0 1405
0 1208
0 1010
0 0813
0 0616
0 0419
0 3800 0 3400 0 3000 0 2600 0 2200 0 1800 0 1400 0 1000 0 600 0 0



TWR-50012

ORIGINAL PAGE IS
OF POOR QUALITY


H-18



TWR-50012

ORIGINAL PAGE IS
OF POOR QUALITY


H-19



TWR-50012

ORIGINAL PAGE IS
OF POOR QUALITY

H-20



TWR-50012


ORIGINAL PAGE IS
OF POOR QUALITY

H-21

T

M-52 SPRAY BOOTH, NORTH DOOR EAST SIDE, ATR LMR 597701.019


12 Apr 90 09:16:29



TWR-50012

ORIGINAL PAGE IS
OF POOR QUALITY

H-22




ORIGINAL PAGE IS
OF POOR QUALITY

TWR-50012

H-23


M-52 SPRAY BOOTH, EAST CEILING #1, ATR CLAMP, LWR 597701.021 12 Apr 90 10 06 53



TWR-50012

H-24

OPTIONAL PAGE F
OF POOR QUALITY




ORIGINAL PAGE IS
OF POOR QUALITY

TWR-50012

H-25

M-52 SPRAY BOOTH, EAST CEILING #3, ATR CLAMP, LWR 587701.023


12 Apr 90 10:37:54



TWR-50012

H-26

ORIGINAL PAGE IS
OF POOR QUALITY




TWR-50012

H-27

ORIGINAL PAGE IS
OF POOR QUALITY


M-52 SPRAY BOOTH, WEST CEILING #1, ATR CLAMP, LWR 587701.025

12 Apr 90 12:07:40



ORIGINAL PAGE IS
OF POOR QUALITY


TWR-50012
H-28




ORIGINAL PAGE IS
OF POOR QUALITY

TWR-50012

H-29




TWR-50012
H-30



ORIGINAL PAGE IS
OF POOR QUALITY

TWR-50012
H-31



Appendix I
Environmental Fallout Panels FTIR Results

REVISION _____

DOC NO. TWR-50012 VOL _____
SEC PAGE I-1

LABORATORY REPORT

12 Apr. 1990

Originator: Joel Ward
Ext 5294, M/S 887A

Request: LWR 600037
Laboratory log # 03-22-90-31788

Subject: FTIR Analysis of NVR and Particulate samples from M-52 Spray Booth
for the presence of Teflon

FTIR analysis has been carried out on NVR fallout samples and particulate samples from the M-52 spray booth. In particular, each sample was checked for the presence of Teflon residue. The presence of Teflon was determined by the appearance of the C-F absorbance peaks at about 1160 and about 1230 wavenumbers.

Sixteen fallout NVR samples and sixteen filter samples were tested.

No Teflon was detected with any of the samples.

Copies of the FTIR spectra are attached.

R. C. Raisor, Spectrochemical Analysis
LAB90099
B1222

After 1st Clean Ar CTP
(^{2nd total})
(1st booth operational cycle)

After 3rd Clean Ar CTP
(4th total)

(2nd booth operational cycle)

M35A LABORATORY

To: Ralph Raisor

From: Joel Ward

Date: 21 March, 1990

Subject: FTIR analysis of NVR from teflon booth

=====

Ralph,


Please perform an FTIR analysis on the following NVR and particulate samples:

<u>sample number</u>	<u>location</u>
1F	freon TF control 1
2F	teflon booth middle, east side
3F	teflon booth north west corner
4F	teflon booth south west corner
5F	teflon booth middle, west side
6F	teflon booth south east corner
7F	teflon booth north east corner
8F I VAL	freon TF control 2
1I N ITIAL	freon TF control 1
2I	teflon booth south east corner
3I	teflon booth south west corner
4I	teflon booth middle, east side
5I	teflon booth middle, west side
6I	teflon booth north east corner
7I	teflon booth north west corner
8I	freon TF control 2

Attach the FTIR spectra to the environmental fallout panel data sheet, return to M-35A ASAP


Thank you,

Joel Ward
Joel Ward



TWR-50012

I-4




TWR-50012

I-5

NVR SAMPLE #31, TEFLON BOOTH SOUTH WEST CORNER, CHCL3/ATR, 6000037.


22 Mar 90 10:29:17




TWR-50012

I-6

NVR SAMPLE #41, TEFLON BOOTH MIDDLE-EAST SIDE, ATR, 600037.004 22 Mar 90 11:17:29




M-52 SPRAY BOOTH, TEFLON BOOTH MIDDLE, WEST SIDE, SAMPLE 5I, 600037
26 Mar 90 08:01:32



TWR-50012

I-8


M-52 TEFLON BOOTH NORTH EAST CORNER, SAMPLE #6I, ATR, 600037. 006
26 Mar 90 08:12:06




TWR-50012

I-9

M-52 TEFLON BOOTH NORTH WEST CORNER, SAMPLE #71, ATR, 600037.007 26 Mar 90 08:45:58



TWR-50012
I-10



TWR-50012

I-11

1688

M-52 FREON TF CONTROL #1, SAMPLE #1F, ATR, LWR 600037.009

26 Mar 90 09:39:07

0

0.0116

0.0185


0.0485

0.0786

0.1086


0.1387

Absorbance



TWR-50012

I-12




TWR-50012

I-13

M-52 TEFLON BOOTH NORTH WEST CORNER, SAMPLE #3F, ATR, 600037.011


26 Mar 90 09:59:06



TWR-50012

I-14


M-52 TEFLON BOOTH SOUTH WEST CORNER, SAMPLE #4F, ATR, 600037.012 26 Mar 90 10:05:34



TWR-50012

I-15


M-52 TEFLON BOOTH MIDDLE WEST SIDE, SAMPLE #5F, ATR, 600037.013 26 Mar 90 10:13:17



TWR-50012

I-16


M-52 TEFLON BOOTH SOUTH EAST CORNER, SAMPLE #6F, ATR, 600037.014 26 Mar 90 10:41:35



TWR-50012


I-17

M-52 TEFLON BOOTH NORTH EAST CORNER, SAMPLE #7F, ATR, 600037.015 26 Mar 90 10:51:35



TWR-50012


I-18



TWR-50012


I-19

M-52 SPRAY BOOTH, FILTER SAMPLE #11, ATR CLAMP, 600037.017
26 Mar 90 11:23:58



TWR-50012

I-20



TWR-50012

I-21

Absorbance

0.7782 0.7494 0.5207 0.3919 0.2632 0.1344 0.057


M-52 SPRAY BOOTH, FILTER SAMPLE #31, ATR CLAMP, 600037.019
26 Mar 90 12:50:55

Wavenumber (cm^{-1})

3800.0 3400.0 3000.0 2600.0 2200.0 1800.0 1400.0 1000.0 600.00

TWR-50012


I-22



TWR-50012

I-23


M-52 SPRAY BOOTH, FILTER SAMPLE #5I, ATR CLAMP, 600037.021
26 Mar 90 13:09:55




TWR-50012

I-24

M-52 SPRAY BOOTH, FILTER SAMPLE #61, ATR CLAMP, LWR 600037.022 26 Mar 90 13:26:53




M-52 SPRAY BOOTH, FILTER SAMPLE #7I, ATR CLAMP, LWR 600037.023 26 Mar '90 13:35:33



TWR-50012


I-26



TWR-50012


I-27

M-52 SPRAY BOOTH, FILTER SAMPLE #1F, ATR CLAMP, LWR 600037.025
26 Mar 90 14:01:06



TWR-50012
I-28


M-52 SPRAY BOOTH, FILTER SAMPLE #2F, ATR CLAMP, LWR 600037.026
26 Mar '90 14:29:15



TWR-50012

I-29

M-52 SPRAY BOOTH, FILTER SAMPLE #3F, ATR CLAMP, LWR 600037.027 26 Mar 90 14:36:32




TWR-50012

I-30

M-52 SPRAY BOOTH, FILTER SAMPLE #4F, ATR CLAMP, LWR 600037.028


26 Mar 90 14:47:20



TWR-50012


I-31

M-52 SPRAY BOOTH, FILTER SAMPLE #5F, ATR CLAMP, LWR 600037.029
27 Mar 90 08:11:19



TWR-50012


I-32



TWR-50012


I-33

M-52 SPRAY BOOTH, FILTER SAMPLE #7F, ATR CLAMP, LWR 600037.031 27 Mar 90 08:35:26




TWR-50012

I-34



TWR-50012

I-35



Appendix J

NVR/Particle Counter Results

REVISION _____

DOC NO. TWR-50012 VOL _____
SEC PAGE
J-1

Final

After Teflon booth clean

Environmental Fallout Panel Data Sheet

Analysis and Results

EFP S/N	Date/ Time Placed	Location	Anal. Date	Particle Count	Particle Matter (mg/m ²)	NVR (mg/m ²)	FTIR Y. attach spectrum	Comments										
(1) 653	21 MAR 90 16:00	M52 Teflon Booth N.C. S.E.	21 MAR 90 05:00	n/a	n/a	0.0		Detectable NVR 1.m. f. is 2.0 mg/m ²										
(2) 654	21 MAR 90 16:00	M52 Teflon Booth N.V. E.	21 MAR 90 05:00	n/a	n/a	0.0		Detectable NVR 1.m. f. is 2.0 mg/m ²										
(3) 655	21 MAR 90 16:00	M52 Teflon Booth N.D. E. SITE Office	21 MAR 90 05:00	n/a	n/a	2.2		Detectable NVR 1.m. f. is 2.0 mg/m ² original										
(4) 655	21 MAR 90 16:00	M52 Teflon Booth N.D. N.E.	21 MAR 90 05:00	n/a	n/a	1.4		Detectable NVR 1.m. f. is 2.0 mg/m ² o. gear										
(5) 666	21 MAR 90 16:00	M52 Teflon Booth SOUTH E. SITE	21 MAR 90 05:00	n/a	n/a	0.0		Detectable NVR 1.m. f. is 2.0 mg/m ² o. gear										
(3) 655P	21 MAR 90 16:00	M52 Teflon Booth Second floor SITE	21 MAR 90 05:00	n/a	n/a	1.0		Detectable NVR 1.m. f. is 2.0 mg/m ² o. gear										

Tritia C

Before the floor boards clearing

Environmental Fallout Panel Data Sheet

Analyses and Results

Date/ EFP S/N	Time Placed	Location	Anal. Date	Particle Count	Particle Matter (mg/m ²)	NVR (mg/m ²)	FTIR (V/m) Y: attach spectrum	Comments
047	18 Feb 90 1000	ms2 Teller South west	18 Feb 90 1400	n/a	n/a	0.4		At 10:00 am 1.0 m. d. is 20 mg/m ²
050	18 Feb 90 1000	Teller South west	18 Feb 90 1400	"	"	0.4		"
053	18 Feb 90 1000	Teller East middle	18 Feb 90 1400	"	"	0.4		"
055	18 Feb 90 1000	Teller west middle	18 Feb 90 1400	"	"	0.4		"
026	18 Feb 90 1000	Teller north east	18 Feb 90 1400	"	"	0.8		"
013	18 Feb 90 1000	Teller North East	18 Feb 90 1400	"	"	0.0		

ORIGINAL PAGE IS
OF POOR QUALITY

----- (CUMULATIVE) -----

LOC		0.5u	0.7u	1.0u	5.0u
25	142366	3269	313	9	
24	43601	792	62	2	
23	246004	4198	332	9	
22	36561	685	72	4	
21	146356	3470	306	11	
20	68253	1601	112	7	
19	228489	4467	293	7	
18	51171	1168	69	3	
17	114718	2680	261	9	
16	47799	875	91	3	
15	155444	3303	344	12	
14	68845	1003	79	5	
13	222737	2897	269	9	
12	70568	1568	167	6	
11	73151	1217	143	6	
10	222361	4168	338	9	
9	70216	1179	88	7	
8	192414	4175	335	11	
7	37932	984	72	2	
6	96886	2977	281	8	
5	145916	5587	298	7	
4	138904	7336	363	6	
3	239488	27380	1018	24	
2	254839	48105	4519	52	
1	322331	106400	40208	127	
MEAN	137494	9659	2017	14	
STDEV	81390	22164	7843	25	

Final results
Environmental particle count


Environmental Fallout Panel Data Sheet

Analysis and Results

EFP S/N	Time Placed	Date/ Time Retrieved	Location	Anal. Date	Particle Count	Particle Matter (mg/m ³)	NVR (mg/m ²)	FTIR (Y/n) y attach spectrum	Sensit. IP - i		COUNT (CUMULATIVE)	
									LIC	LIC	0.5u	0.7u
C1/C	15 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				166116	4637
C1/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				192360	338
C1/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				54951	115
C1/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				190118	5385
C1/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				167161	4218
C1/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				146801	3019
C2/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				197823	4319
C2/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				52933	1104
C2/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				208618	4892
C3/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				16221	160
C4/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				155645	3833
C4/C	16 Apr '90	16 Apr 1990	Telluric beach S. E.	17 Apr 1990	n/a	n/a	0.0				77402	1118
											256036	484
											74594	91
											21187	217
											165524	2518
											99702	394
											45756	3860
											400686	55158
											3766	27
											31279	119341
											157466	11161
											16645	4745
											STEN	166730

HIBURNE PARTICLE COUNTER - NET2000

16 Apr / 1990 mes 2 tether built



Appendix K
NASA Test Box Results/FTIR Scans

REVISION _____

DOC NO. TWR-50012 VOL _____
SEC PAGE
K-1

Page 73 of 52 for Job No. 3

LABORATORY WORK REQUEST

584093

FROM: SOUTHERN	EXTENSION: 2011	COST CENTER: 1051	PROJECT NO.:	TASK	SUBTASK
ORGANIZATION: D	MAIL STOP:	WORK ORDER NO.		USER	PCN

SAMPLE INFORMATION

SAMPLE DESCRIPTION	<input type="checkbox"/> RAW MATERIAL <input type="checkbox"/> INPROCESS <input type="checkbox"/> POST PROCESS	DATE	
PART NO STOCK NO.	SERIAL NO /LOT NO.	ASSEMBLY PART NO.	ASSEMBLY SERIAL NO.
MIX	GRIND	SAMPLED BY	

TEST REQUIRED OR DESCRIPTION OF WORK REQUIRED. INCLUDE REASON FOR REQUEST

1. Please check this ~~biased~~ ~~relic~~ ~~filter~~ for teflon and tecron products as per teflon procedure (suggestion of J. Dietz and R.D. Law). Please list results.

2. NASA Test Box

3. Before Cranking, results

4. 1st CTP

5.

6.

7.

8.

REPORT RESULTS TO: Monte Scothern	SEND COPY TO	RESULTS DESIRED BY (SPECIFIC DATE) 2 March 90
AUTHORIZED SIGNATURE OR INSPECTION STAMP <i>Monte Scothern</i>		

FOR LABORATORY USE ONLY

SPECIAL INSTRUCTIONS

RESULTS OF LABORATORY ANALYSIS

No Teflon detected by FTIR analysis
FTIR spectra are attached


DISPOSITION

ACCEPT REJECT RESAMPLE

DATE AND TIME COMPLETED	TIME REQUIRED	DATE REPORTED	SIGNATURE
-------------------------	---------------	---------------	-----------

TWR-50012


K-2



TWR-50012

K-3


BLEEDER CLOTH FILTER, ATR CLAMPED, LWR 584093.001 20 Feb 90 12:57:21



ORIGINAL PAGE IS
OF POOR QUALITY


TWR-50012

K-4



TWR-50012

K-5



TWR-50012

K-6

ADVANCED TECHNOLOGY
LABORATORY SERVICES

LABORATORY REPORT

06 Apr. 1990

Originator: R. W. Jessop
Ext. 6238, M/S 695

Request: LWR 594129
Laboratory Log # 03-01-90-31743

Subject: FTIR Analysis of Bleeder Cloth Filter for Teflon

The FTIR spectrum of the bleeder cloth was obtained by clamping the material against an ATR crystal. No Teflon was detected on the sample.

A copy of the FTIR spectrum is attached.

Nasa Test box
After cleaning, results
Final


R. C. Raisor, Spectrochemical Analysis
LAB90093
B1143

LABORATORY WORK REQUEST

531129

FROM R. S. Wilson	EXTENSION 6006	COST CENTER 6950	PROJECT NO.	TASK	SUBTASK
ORGANIZATION FBI - BIRMINGHAM	MAIL STOP 100	WORK ORDER NO. 111-12		USER	PCN

SAMPLE INFORMATION

SAMPLE DESCRIPTION		MANUFACTURER / DESTINATION	DATE
100% clean office		<input type="checkbox"/> RAW MATERIAL <input checked="" type="checkbox"/> INPROCESS <input type="checkbox"/> POST PROCESS	March 11, 1997
PART NO./STOCK NO.	SERIAL NO./LOT NO.	ASSEMBLY PART NO.	ASSEMBLY SERIAL NO.
MIX	GRIND	SAMPLED BY	

TEST REQUIRED OR DESCRIPTION OF WORK REQUIRED. INCLUDE REASON FOR TEST

- ANALYSIS OR DESCRIPTION OF WORK REQUIRED. INCLUDE REASON FOR REQUEST
1. Analysis this bleeder cloth filter for teflon residue per J. Dietz please list results.

REPORT RESULTS TO	SEND COPY TO	RESULTS DESIRED BY (SPECIFIC DATE)
R. W. Jessop m/s 695	S. Goleniewski m/s L72	ASAP or 22 march 1990
AUTHORIZED SIGNATURE OR INSPECTION STAMP		

FOR LABORATORY USE ONLY

SPECIAL INSTRUCTIONS

SEND COPY TO

RESULTS DESIRED BY SPECIFIC DATE

ASAP 00 22 March 1990

AUTHORIZED SIGNATURE OR INSPECTION STAMP

SPECIAL INSTRUCTIONS

DISPOSITION

ACCEPT REJECT RESAMPLE

RESULTS OF LABORATORY ANALYSIS

DATE AND TIME COMPLETED

70247-000


— 1 —

SIGNATURE

TWR-50012

K-8

ORIGINAL PAGE IS
OF POOR QUALITY



TWR-50012

ORIGINAL PAGE IS
OF POOR QUALITY

K-9

LABORATORY WORK REQUEST

OU-16 90-32³12
594134

TO:

Jim Dietz

FROM:	EXTENSION	COST CENTER	PROJECT NO.	TASK	SUBTASK
R. W. Jessop	6238	6953			
ORGANIZATION	MAIL STOP	WORK ORDER NO.		USER	PCN
Cont. control Mfg. Engineering	695	B1143			

SAMPLE INFORMATION

SAMPLE DESCRIPTION		<input type="checkbox"/> RAW MATERIAL	DATE
Air Weave Bleeder Cloth		<input checked="" type="checkbox"/> INPROCESS	16 April 1990
		<input type="checkbox"/> POST PROCESS	
PART NO./STOCK NO.	SERIAL NO./LOT NO.	ASSEMBLY PART NO.	ASSEMBLY SERIAL NO.
MIX	GRIND	SAMPLED BY	

TEST REQUIRED OR DESCRIPTION OF WORK REQUIRED. INCLUDE REASON FOR REQUEST

1. Analysis ~~the~~ this bleeder cloth filter for teflon residue per J. Dietz please list results.
 2.

*Test Box Filter**After dome process, Final*

- 3.
- 4.
- 5.
- 6.
- 7.
- 8.

REPORT RESULTS TO	SEND COPY TO	RESULTS DESIRED BY (SPECIFIC DATE)
R. W. Jessop m/s 695		ASAP 18 April 1990
AUTHORIZED SIGNATURE OR INSPECTION STAMP		

FOR LABORATORY USE ONLY

SPECIAL INSTRUCTIONS

RESULTS OF LABORATORY ANALYSIS

*NO teflon detected by FTIR analysis
J.C.H.*

DISPOSITION

 ACCEPT REJECT RESAMPLE

DATE AND TIME COMPLETED

TIME REQUIRED

DATE REPORTED

SIGNATURE


TWR-50012

FORM TC 716 (REV 2-86)

K-10


ORIGINAL PAGE IS
OF POOR QUALITY

AIR WEAVE BLEEDER CLOTH, M-52 SPRAY BOOTH, ATR CLAMP, 594134.001 17 Apr 90 08:58:51



TWR-50012

K-11



Appendix L
Witness Panel Pull Test Data

REVISION _____

DOC NO. TWR-50012 | VOL _____
SEC _____ PAGE _____
L-1

LABORATORY WORK REQUEST

600021

32427

HESSEL TEST LAB

FROM 1. HESSEL	EXTENSION 5670	COST CENTER 12412	PROJECT NO 44301	TASK 10	SUBTASK 1
ORGANIZATION 1. HESSEL TEST LAB	MAIL STOP 102	WORK ORDER NO 012		USER IPCN	

SAMPLE INFORMATION

SAMPLE DESCRIPTION 1. EASY RELEASE TAPE - 100% POLYESTER 2. EASY RELEASE TAPE - 100% POLYESTER	RAW MATERIAL <input checked="" type="checkbox"/> INPROCESS <input type="checkbox"/> POST PROCESS	DATE 18 APRIL 90	
PART NO STOCK NO TEXTILE PLATE PEEL MIX # 0001644 # 0001655	SERIAL NO LOT NO 0001686 0001677	ASSEMBLY PART NO /	ASSEMBLY SERIAL NO 111

TEST REQUIRED OR DESCRIPTION OF WORK REQUIRED INCLUDE REASON FOR REQUEST

1. TENSILE TEST @ 90°
2. TENSILE TEST @ 45° IN 100% POLYESTER TAPE
3. TENSILE TEST @ 45° PEEL TEST @ 90° IN 100% POLYESTER TAPE
4. CONTACT TEAR TEST @ 90° IN 100% POLYESTER TAPE
5. REPORT : RAIN DATA / DATA SUMMARY / STATISTICS (6 PAGES)
6. MODE OF FAILURE DOCUMENT AS NEEDED

REPORT RESULTS TO 1. HESSEL	SEND COPY TO	RESULTS DESIRED BY SPECIFIC DATE L-11-90
AUTHORIZED SIGNATURE OR INSPECTION STAMP J. G. HESSEL		

FOR LABORATORY USE ONLY

SPECIAL INSTRUCTIONS
Sample was not
original

RESULTS OF LABORATORY ANALYSIS

NOTE: BUTTON STRESS (PSI)
ON PAGE 3, 4, 5 OF REPORT
HAS BEEN CORRECTED TO
REFLECT DIAMETER OF 1.250"
INSTEAD OF 1.234" AS
ORIGINALLY CALCULATED.

DISPOSITION

 ACCEPT REJECT RESAMPLE

DATE AND TIME COMPLETED	TIME REQUIRED	DATE REPORTED	SIGNATURE	TWR-50012
-------------------------	---------------	---------------	-----------	-----------

FORM TC 716 (REV 2/86)

L-2

ORIGINAL PAGE IS
OF POOR QUALITY

Date: 6-10-91
Technician: D. H. JONES
Character: V. HEUSSER

1 = Adhesive/Adhesive
2 = Cohesive/Adhesive
3 = Adhesive/Epoxy
4 = Cohesive/Epoxy

Failure Mode Key:
5 = Cohesive/Rubber
6 = Adhesive/Rubber
7 = Cohesive/Liner
8 = Adhesive/Liner
9 = Joint
10 = Failure, Liner
11 = Tab Break
9 = Tab Side
P = Panel Edge

Date: 6-10-91
Technician: D.

Test Machine: SALOMON
Test Type: Tensile Adhesion

Temperature: 75 Deg. F
Crosshead Speed: .05 In/sec

Test No.	Segment ID.	Panel ID.	Serial	Dia (in)	Section (in ²)	Load (lbs)	Stress (psi)	Failure Mode Analysis									
								1	2	3	4	5	6	7	8	9	10
1			0001644	1.12838	1.000	3225	3225	95	5								8
2			0001644	1.12838	1.000	3014	3013	100									P
3			0001644	1.12838	1.000	2421	2421	100									P
4			0001644	1.12838	1.000	3113	3113	100									P
5			0001644	1.12838	1.000	3436	3436	95	5								P
6			0001644	1.12838	1.000	3617	3617	100									S
7			0001644	1.12838	1.000	3318	3318	100									P
8			0001644	1.12838	1.000	3696	3696	95	5								P
9			0001644	1.12838	1.000	2005	2005	100									B
10			0001644	1.12838	1.000	3565	3564	97	1								S
11			0001644	1.12838	1.000	2451	2451	100									B
12			0001644	1.12838	1.000	2468	2469	95									S
13			0001644	1.12838	1.000	2615	2615	95	5								B
14			0001644	1.12838	1.000	3535	3535	95	5								S
15			0001644	1.12838	1.000	2685	2685	95									S
16			0001644	1.12838	1.000	2281	2281	97									B
17			0001644	1.12838	1.000	2987	2987	100									P
18			0001644	1.12838	1.000	2773	2773	100									P
19			0001644	1.12838	1.000	3289	3289	94	3								S
20			0001644	1.12838	1.000	2404	2404	100									S
21			0001644	1.12838	1.000	3078	3078	100									B
22			0001644	1.12838	1.000	3242	3242	100									E
23			0001644	1.12838	1.000	2984	2984	95	2								Z
24			0001644	1.12838	1.000	1853	1853	100									B
Average (PSI):								2914	99	1							1
Standard Deviation:								514.0									
Coeff. of Var:								17.6									

Prepared by the Mechanical Properties Characterization Section of the E&E Laboratories

TWR-50012

PAGE 1

L-3

ORIGINAL PAGE IS
OF POOR QUALITY

Part #: A00621
 Part Order: 81179
 Originator: V. HEUSSER

1 = Adhesive/Metal	Failure Mode Key
2 = Adhesive/Adhesive	5 = Cohesive/Rubber
3 = Adhesive/Phenolic	6 = Adhesive/Rubber
4 = Cohesive/Phenolic	7 = Cohesive/Liner
	8 = Adhesive/Liner
	9 = 010
	10 = Failure (assent)
	79 = Iso Broke
	8 = Button side
	F = Panel Side

Date: 4-19-90
 Technician: CD

Test Machine: SAL300H

Temperature: 75 Deg. F
 Crosshead Speed: .05 in/min

Test No.	Segment ID.	Panel ID. Serial	Dia (in)	Cross Section (in2)	Max Load (lbs)	Max Stress (psi)	Failure Mode Analysis									
							1	2	3	4	5	6	7	8	9	10
25		0001615	1.12838	1.000	3113	3113	80	20								
* 26		0001615	1.12838	1.000	3974	3974	55	25								
29		0001615	1.12838	1.000	3037	3037	65	10								
30		0001615	1.12838	1.000	3623	3623	80	40								
* 31		0001615	1.12838	1.000	2087	2087	25	25								
* 32		0001615	1.12838	1.000	3805	3805	70	20								
33		0001615	1.12838	1.000	3441	3441	70	30								
34		0001615	1.12838	1.000	4297	4297	72	20								
35		0001615	1.12838	1.000	4069	4069	50	42								
* 36		0001615	1.12838	1.000	3248	3248	25	55								
37		0001615	1.12838	1.000	3822	3822	50	40								
38		0001615	1.12838	1.000	4063	4063	60	35								
* 39		0001615	1.12838	1.000	2193	2193	40	5								
* 40		0001615	1.12838	1.000	1407	1407	10	30								
* 41		0001615	1.12838	1.000	3236	3236	40	25								
42		0001615	1.12838	1.000	3957	3957	45	55								
43		0001615	1.12838	1.000	4139	4139	70	27								
44		0001615	1.12838	1.000	4209	4209	55	45								
45		0001615	1.12838	1.000	4373	4373	90	10								
46		0001615	1.12838	1.000	3412	3412	87	10								
47		0001615	1.12838	1.000	4069	4069	40	60								
48		0001615	1.12838	1.000	4502	4502	80	15								

Average (FSD):

3975

67 31

2

Standard Deviation:

452.8

Coeff. of Var:

11.7

* Excluded from average

Prepared by the Mechanical Properties Characterization Section of the R&D Laboratories

PAGE 2

TWR-50012

L-4

ORIGINAL PAGE IS
 OF POOR QUALITY

LWR #: 500021
 Work Order #: 81139
 Originator: V. HEUSSER

1 = Adhesive/Metal	Failure Mode:	1 = Void
2 = Cohesive/Adhesive	5 = Cohesive/Polymer	10 = Failure Comment
3 = Adhesive/Thermoplastic	6 = Adhesive/Polymer	1B = Tab Broke
4 = Cohesive/Thermoplastic	7 = Cohesive/Liner	8 = Button Side
	9 = Adhesive/Polymer	P = Panel Side

Date: 04-20-93 Test Machine: RIEHLE Temperature: 75 Deg. F
 Technician: LD.WALTERS Test Type: Tensile Cohesion Crosshead Speed: .5 in/min

Test No.	Segment ID.	Panel ID. Serial	Dia (in)	Section	Cross	Max	Max	Failure Mode Analysis								
					Load (lbf)	Stress (psi)	1	2	3	4	5	6	7	8	9	10
1		0001677	1.05000	1.227	1044	851										100
2		0001677	1.05000	1.227	1064	867										100
3		0001677	1.05000	1.227	1054	853										100
4		0001677	1.05000	1.227	756	779										100
5		0001677	1.05000	1.227	828	726		8								P
6		0001677	1.05000	1.227	937	763		5								P
7		0001677	1.05000	1.227	1036	893										100
8		0001677	1.05000	1.227	1037	845										100

Average (PSI):

823

2

38

Standard Deviation:

58.9

7.2

Coeff. of Var:

Date: 04-19-93 Test Machine: RIEHLE Temperature: 75 Deg. F
 Technician: LD.WALTERS Test Type: 45 Degree Peel Crosshead Speed: 2.0 in/min

Test No.	Segment ID.	Panel ID. Serial	Width (in)	Min Stress (pli)	Max Stress (pli)	Avg Stress (pli)	Inches Peeled	Failure Mode Analysis								
				1	2	3	4	5	6	7	8	9	10			
1	45 DEG. PEEL	0001677	1.00000	171.3	182.7	179.1	3.4									100
2	45 DEG. PEEL	0001677	1.00000	174.5	180.4	183.4	3.2									100
3	45 DEG. PEEL	0001677	1.00000	171.2	184.5	177.7	3.0									100
4	45 DEG. PEEL	0001677	0.35000	174.7	187.0	180.0	3.2									100
5	45 DEG. PEEL	0001677	1.00000	163.3	186.5	180.7	3.6									100
6	45 DEG. PEEL	0001677	0.38000	164.7	183.2	178.1	3.2									100
7	45 DEG. PEEL	0001677	1.00000	157.7	184.0	174.1	3.2									100

Average:

169.1

185.6

173.0

6.0

2.6

3.0

3.58

1.41

1.65

Prepared by the Mechanical Properties Characterization Section of the R&D Laboratories

PAGE 3

TWR-50012

L-5

ORIGINAL PAGE IS
 OF POOR QUALITY

LWR #: 500021
 Work Order: B1138
 Originator: V. NEUSSER

1 = Adhesive/Metal
 2 = Cohesive/Adhesive
 3 = Adhesive/Phenolic
 4 = Cohesive/Phenolic
 5 = Cohesive/Rubber
 6 = Adhesive/Rubber
 7 = Cohesive/Liner
 8 = Adhesive/Liner
 9 = Void
 10 = Failure Comment
 TB = Tab Broke
 B = Button Side
 P = Panel Side

Date: 04-20-90
 Technician: LD.WALTERS

Test Machine: RIEHLE
 Test Type: Tensile Adhesion
 Temperature: 75 Deg. F
 Crosshead Speed: .5 in/min

Test No.	Segment ID.	Panel ID.	Serial	Dia (in)	Cross Section (in ²)	Max Load (lbs)	Max Stress (psi)	Failure Mode Analysis										
								1	2	3	4	5	6	7	8	9	10	
9		0001636		1.25000	1.227	1017	829		4		96							
10		0001636		1.25000	1.227	1027	837					100						
11		0001636		1.25000	1.227	917	747					100						
12		0001636		1.25000	1.227	995	811		2		98							p
13		0001636		1.25000	1.227	1049	855					100						
14		0001636		1.25000	1.227	983	801		2		98							p
15		0001636		1.25000	1.227	1030	839					100						
16		0001636		1.25000	1.227	1050	856					100						

Average (PSI):

822

1

Standard Deviation:

35.6

Coeff. of Var:

4.3

Date: 04-19-90
 Technician: LD.WALTERS

Test Machine: RIEHLE
 Test Type: 45 Degree Peel
 Temperature: 75 Deg. F
 Crosshead Speed: 2.0 in/min

Test No.	Segment ID.	Panel ID.	Serial	Width (in)	Min Stress (pli)	Max Stress (pli)	Avg Stress (pli)	Inches Peeled	Failure Mode Analysis									
									1	2	3	4	5	6	7	8	9	10
9	45 DEG. PEEL	0001636		1.0200	145.6	165.7	158.3	3.6										100
3	45 DEG. PEEL	0001636		0.9300	156.5	168.3	163.1	3.4										100
10	45 DEG. PEEL	0001636		1.0000	152.8	165.1	158.8	3.5										100
11	45 DEG. PEEL	0001636		1.0400	148.3	165.8	160.1	3.4										100
12	45 DEG. PEEL	0001636		0.9600	162.1	172.4	167.8	3.2										100
13	45 DEG. PEEL	0001636		1.0300	151.9	171.2	163.5	4.2										100
14	45 DEG. PEEL	0001636		1.0300	150.5	157.2	153.9	2.3										100

Average:

152.5

168.0

161.6

100

Standard Deviation:

5.4

2.9

3.4

Coeff. of Var:

3.57

1.70

2.89

Prepared by the Mechanical Properties Characterization Section of the R&D Laboratories

PAGE 4

TWR-50012

L-6

ORIGINAL PAGE IS
 OF POOR QUALITY

WR #: 600021
Work Order: B1138
Originator: V. HEUSSE

Failure Mode Key									
1 = Adhesive/Metal				5 = Cohesive/Rubber				9 = Void	
2 = Cohesive/Adhesive				6 = Adhesive/Rubber				10 = Failure Comment	
3 = Adhesive/Phenolic				7 = Cohesive/Liner				TB = Tab Broke	
4 = Cohesive/Phenolic				8 = Adhesive/Liner				B = Button Side	
								P = Panel Side	

Date: 04-20-90
Technician: LD.WALTERS

Test Machine: RIEHLE
Test Type: Tensile Adhesion

Temperature: 75
Crosshead Speed: .5
Deg. F
in/min


Test No.	Segment ID.	Panel ID. Serial	Dia (in)	Cross Section (in ²)	Max Load (lbs)	Max Stress (psi)	Failure Mode Analysis										
							1	2	3	4	5	6	7	8	9	10	
17		0001723	1.25000	1.227	1081	881		3		37						P	
18		0001723	1.25000	1.227	1064	867				103							
19		0001723	1.25000	1.227	1053	863		3		37						P	
20		0001723	1.25000	1.227	1076	877				100							
21		0001723	1.25000	1.227	1012	825		5		35						P	
22		0001723	1.25000	1.227	1012	825				100							
23		0001723	1.25000	1.227	1074	875				100							
24		0001723	1.25000	1.227	1042	849				100							
Average (PSI):						858		1		39							
Standard Deviation:						22.4											
Coeff. of Var:						2.6											

Date: 04-19-90
Technician: LD.WALTERS

Test Machine: RIEHLE
Test Type: 45 Degree Peel

Temperature: 75
Crosshead Speed: 2.0
Deg. F
in/min

Test No.	Segment ID.	Panel ID. Serial	Width (in)	Min Stress (pli)	Max Stress (pli)	Avg Stress (pli)	Inches Peeled	Failure Mode Analysis										
								1	2	3	4	5	6	7	8	9	10	
15	45 DEG. PEEL	0001723	1.00000	157.2	169.4	164.0	4.8		3		97							
16	45 DEG. PEEL	0001723	0.98000	154.8	170.3	165.0	3.3				100							
17	45 DEG. PEEL	0001723	1.00000	157.0	171.0	165.5	3.9		3		97							
18	45 DEG. PEEL	0001723	0.98000	157.3	171.7	165.7	4.1				100							
19	45 DEG. PEEL	0001723	1.00000	155.2	172.0	166.3	3.2		2		98							
20	45 DEG. PEEL	0001723	1.00000	158.3	175.7	168.7	3.5				100							
21	45 DEG. PEEL	0001723	1.00000	153.9	173.8	164.4	3.9				100							
Average:						156.3	171.3	165.7		1		99						
Standard Deviation:						1.7	2.2	1.5										
Coeff. of Var:						1.88	1.28	0.93										



Appendix M
Engineering Evaluation Results

REVISION _____

DOC NO. TWR-50012 VOL _____
SEC PAGE _____
M-1

Thiokol CORPORATION
SPACE OPERATIONS

10 May 1990
L623-FY90-M142

TO: Distribution
FROM: V. Fitch
Thermal Insulation Design
SUBJECT: CTP-0142A, Revision B Justification
REFERENCE: L623-FY90-M134, 'CTP-0142, Bond Strength Test Results,
V. Fitch, 24 April 1990

1.0 INTRODUCTION

The M-52 spray booth qualification test for paint and Chemlok application processes of domes was conducted per CTP-0142A. The spray booth passed all tests, except, it did not pass the paragraph 8.2.2A test of the CTP. In accordance with paragraph 8.2.2A, two each NBR insulation to steel and steel epoxy steel (systems tunnel type III) witness panels were processed simultaneously with the test dome. The insulation witness panels represented the dome process configuration and the epoxy witness panels provided a sensitive bond system for discrimination of contaminants in the spray booth.

The insulation witness panels had acceptable bond strengths when compared against the established RSRM witness panel data base. The epoxy witness panels did not have acceptable bond strength when compared against the established RSRM witness panel data base. A subsequent investigation identified circumstances that could account for the unacceptable bond strengths of the epoxy witness panels. An engineering evaluation test was conducted that verified the cause and affect relationship between the circumstances and the bond strengths of the epoxy witness panels.

2.0 OBJECTIVE

The objective of this memo is to disseminate the events and rationale that drove revision B of CTP-0142A.

3.0 SUMMARY

The introduction of adverse bonding variables to the CTP epoxy witness panel test mitigates this test failure. The wrongly introduced variables had a detrimental effect on the bond strength of the epoxy witness panels as evidenced by the engineering evaluation test. Had the variables not been wrongly introduced, the test of epoxy witness panels would not have failed.

Printed by the Thiokol Computer System on 10 MAY 1990

A023243a

REVISION

DOC NO. TWR-50012 VOL
SEC PAGE M-2

ORIGINAL PAGE IS
OF POOR QUALITY

4.0 CONCLUSIONS

The epoxy witness panels were adversely affected by process variables wrongly introduced to the test that were not associated with the test objectives and, hence, a "no test" declaration for the epoxy witness panel portion of the CTP is justified.

Comparison of the CTP epoxy witness panels with the established RSRM systems tunnel witness panel data base is erroneous.

5.0 RECOMMENDATIONS

Perform a re-test of the epoxy witness panels.

Revise the epoxy witness panel test method and the CTP accordingly.

Compare test results against a control set instead of the systems tunnel witness panel data base.

6.0 DISCUSSION

Reference 1 details the CTP epoxy witness panel test results, the wrongly introduced test variables, and the engineering evaluation test procedure. These items are recapped below.

The insulation witness panels predominantly had cohesive failure and elastomer strength consistent with the established RSRM witness panel data base. The average tensile adhesion strengths were 823 and 822 psi and the average peel strengths were 179 and 162 pli (LWR-600021). The data base mean are 756 psi and 172 pli. The epoxy witness panels predominantly had adhesive failure and averaged bond strength that was not within 5 standard deviations of the established RSRM data base mean. The average tensile adhesion strengths were 2914 and 3875 psi (LWR-600021). The data base mean is 5588 psi and the mean less five standard deviations is 3734 psi.

The high occurrence of epoxy witness panel adhesive failure prompted concern about witness panel preparation. Three variables were identified as being wrongly introduced to the test. 1) The bond surfaces of the panels were not prepared with silane primer (adhesion promoter applied to the systems tunnel case bond surface and witness panels). Silane primer precludes adhesive failure by masking minor surface contamination effects. 2) The panels remained in the spray booth for upwards of a week prior to assembly. The steel bond surface had ample time to oxidize. Oxidation will lower the applicable epoxy to steel bond strength. Additionally, the test environment of the panels was not controlled and the distinct possibility exists that adverse unknown variables were introduced. 3) The prepared witness panel bond surfaces were covered with "black poly" while on the panel holder (the Chemloked panels were left on the floor and uncovered). Manufacturing procedures do not allow prepared bond surfaces to be in contact with black poly. This procedure was established after a similar incident when the bond strength of Chemloked witness panels was suspected as being adversely effected by transference of contamination from black poly.

A023243a

The engineering evaluation test objective was to account for the effects of the test variables introduced during the CTP testing. Preparation of the bond specimens is discussed below.

- 1) 2 freshly grit blasted and methyl chloroform vapor degreased witness panels (designated A and B) were placed in the spray booth and exposed to a spray booth operational cycle. The operational cycle simulates the external paint cure cycle and consists of having the make-up air fans on with booth temperature at 135°F for 5 hours.
- 2) 2 freshly grit blasted and methyl chloroform vapor degreased witness panels (designated C and D) were placed outside of the spray booth in the M-52 surge area and exposed to ambient conditions (facility control).
- 3) 2 freshly grit blasted and methyl chloroform vapor degreased witness panels (designated E and F) were assembled in the laboratory along with the aforementioned panels (lab control).
- 4) The bond surfaces of panels A - D & F were not silane primed but the bond surface of panel E was silane primed. All tensile buttons were silane primed to force the failure to the panel side. Following a 24 hour ambient cure the tensile buttons were pull tested at a 0.05 inch per minute pull rate.

The engineering evaluation test results are listed below.

PANEL	EXPOSURE	TENSILE (psi)	% ADHESIVE FAILURE
A	BOOTH CYCLE	4225	21
B	BOOTH CYCLE	4185	25
C	M-52 AMBIENT	3893	40
D	M-52 AMBIENT	3850	49
E	LAB CONTROL, No. 1	5386	0
F	LAB CONTROL, No. 2	3652	34

The conclusions derived through this test are listed below.

- 1) The spray booth environment exposed panels had significantly greater bond strength than the surge area environment exposed panels. This indicates that the spray booth will provide a better bonding environment for domes than is currently available for case hardware.
- 2) The silane primer increased the bond strength 50% for the control panels. This indicates that silane primer would have significantly increased the bond strength of the CTP witness panels.

A023243a

REVISION _____

DOC NO. TWR-50012 | VOL _____
SEC _____ PAGE _____ M-4

- 3) The spray booth panels had greater strength during the engineering evaluation test than they did during the CTP test. This indicates that the controlled test minimized the effect on bond strength from oxidation, "black poly", and/or unknown variables.

The engineering evaluation test provides sufficient justification to repeat the epoxy witness panel test. Scrutiny of the CTP test procedure following the engineering evaluation test lead to the conclusion that the CTP test method was flawed. Nor should its results be compared with the systems tunnel data base for acceptance. The reasons for this are 1) systems tunnel data base for acceptance. The reasons for this are 1) silane primer precludes surface contamination effects and discrimination of surface contamination effects is the objective of the test, 2) time lines of systems tunnel surface preparation to primer application and dome surface preparation to panel primer application are not consistent which introduces the oxidation variable, and 3) systems tunnel panels are prepared in final assembly and the CTP test panels are prepared in the lab which introduces a human and facility variable.

Revision of the test procedure was prudent. The re-test is designed to isolate the spray booth environment exposure variable. Panels (5 total) exposed to the spray booth environment will be statistically compared against control panels not exposed to the spray booth environment (5 total). Should the spray booth exposed panels have significantly lower bond strength than the control panels, the test has failed (Significantly lower bond strength was defined at the 95% confidence level during the CTP-0142B TRR). All other process variables will be a constant for both panel sets. The panel bond surface will not be silane primed for the primer masks contaminants. All tensile buttons will be silane primed to ensure that any adhesive failure occurs on the panel side.

The dome is not required per CTP-0142B to be re-processed during this re-test. A spray booth operational cycle of make-up air fans on and booth temperature at 135°F for 4 to 5 hours is specified and will suffice. The ability to process the dome in the spray booth has been identified. The issue to be addressed by this test is whether or not there are contaminants indigenous to the spray booth that could become airborne and be deposited on dome bond surfaces during processing and that would adversely affect the NBR to steel bond strength.

The proposed test as discussed and the revision to the CTP were approved via TRR Wednesday, 9 May.

John W. Fitch
Fitch

Approved by:

F. B. Baugh
F. B. Baugh, Supervisor
Thermal Insulation Design

VWF/pn

A023243a

<u>Distribution</u>	<u>M/S</u>
L. Allred	L72A
B. Andersen	650
F. Baugh	L62B
D. Call	692
J. Daines	L61
D. Earl	692
N. Eddy	L62B
V. Fitch	L62B
S. Foth	811
R. Furrows	L72
L. Manuel	L71
R. Marsh	E63
S. Mildenhall	L90
P. Petty	L82
R. Raisor	245
C. Whitworth	L90
K. Wilks	E63
R. Wilks	L62

Appendix N

CTP-0142, Revision A, Conscan Data

REVISION _____

DOC NO. TWR-50012 | VOL _____
SEC | PAGE _____
N-1

DATE 4/07/90 MMS13.1A SHO TRAVELER ** DUPLICATE **

PAGE 121

PART NO.: 2182C7C-01(910) L

SERIAL/LUT: 0000002 000000?

CPI RV OPERATION 1250 APR 13
HR61A 00 CNSCAN

WORK ORDER PROD CTL C/C CYL HRS MFG Q-A
HR61A 00 0001 6541 STP DATE STP DATE

STEP 350 I ASSEMBLIES

PROCESS PER ENGINEERING DIRECTION. ENGINEERING
INFORMATION ONLY.

CCNSCAN PANELS PER DI-1014. RECORD DATA FROM POINTS 1-5 AS
REFERRED IN SKETCH PANEL SAMS-02. RECORD S/N AND READINGS FROM
EACH POINT AND AVG READINGS BELOW.

NOTE: DO NOT CLEAN PANELS BEFORE CONSCANNING.

PANEL	ID	S/N	1	2	3	4	5	Avg.
A10001696	9222	832	658	817	832	832	832	832
B10001723	783	847	749	729	838	790	790	790
C10001677	645	725	822	851	868	792	792	792

390

ORIGINAL PAGE
OF POOR QUALITY

370

30319
APR 16

30319
APR 16

RFQUT RFN ----- WIT REQUIRED ✓-----

CLEAN WITNESS PANELS USING THE FOLLOWING METHODS UNTIL READING
IS AVERAGE 17:

1. WIPE THE PANELS WITH ULTRA FINE SCOTCHBRITE.
2. DOUBLE WIPE THE AREA USING TCA AND RYMPLECLINTH.

390

REQUIRED ----- WIT REQUIRED ✓-----

30319
APR 16

CCNSCAN THE PANELS PER DI-1014 IF THE WITNESS PANELS ARE RECLEANED.
RECCPD THE DATA FROM POINT 1-5 AS REFERENCED IN SKETCH PANEL SAMS-02.
REFORD THE S/N AND READINGS FROM EACH POINT AND AVG READING BELOW.

TWR-50012
N-2

OPERATION: 100

DATE 4/02/90 PART NO.: 71132C29-C1(910) L - SERIAL/LOT: 0000002 0000002

CPI RV OPERATION 15510 APR 18

HR61A 0.0 100 CONSCAN

STEP 345 INSTRUCTIONS

2. OCURLE WIPE USING RYMPLECLOTH DAMPENED WITH TCA.

QC, HAVE MFG RE-CLFAN AREAS WHERE CONSCAN READING IS BELOW 378. UNTIL ACCEPTABLE READING (ABOVE 378) IS OBTAINED, CONSCAN AGAIN AND RECORD ACCEPTABLE READINGS. IN AN EFFORT TO OBTAIN CONCLUSIVE DATA FOR COMPARISON FROM END OF DECREASE READINGS IT IS NECESSARY TO TRY TO ESTABLISH THE SAME GENERAL LOCATION TO OBTAIN BOTH SETS OF MEASUREMENTS. THE FOLLOWING PROCEDURE SHOULD BE USED TO OBTAIN THE PEAK AND HOLD MEASUREMENTS USING THE ONE INCH SENSOR AND THE • 25 INCH STANDOFF. QC, PRIOR TO CHEMLOK APPLICATION THE FOLLOWING MEASUREMENT WILL BE TAKEN. TEMPERATURE OF CASE MUST BE 50-104 DEG F. RECORD CASE TEMPERATURE. 72.

BEFORE 78 AFTER 72

CPTAIN ONE READING AS CLOSE TO THE DOME END AS POSSIBLE AND EASURE THAT IT IS ON A FLAT INSULATION BONDING SURFACE. THESE READINGS ARE REQUIRED AT THE FOLLOWING ANGULAR LOCATIONS AND THE SPECIFIED LONGITUDINAL LOCATIONS.

DGREE AS CLOSE AS TWO FEET FOUR FEET AS CLOSE AS PRACTICAL TO FRONT FWD FRONT FWD PRACTICAL TO FWD END END NOZZLE BOSS


c 497 559 476 473

45 466 492 550 464
SC 443 514 575 553
115 482 530 533 268
180 424 519 551 981
225 451 567 552 598
270 415 469 469 509
315 491 505 472 517

QC NOTE: ALL STEPS MAY OR WILL BE DEVIATED FROM DURING THIS

TWR-50012
N-3

ORIGINAL PAGE IS
OF POOR QUALITY



Appendix O

Postperformance Fallout Panel FTIR Data

REVISION

DOC NO. TWR-50012 | VOL
SEC | PAGE
O-1

Final Results, Fall-out pane. (FTIR NVR)
after booth off-cycle

LABORATORY REPORT

20 Apr. 1990

Originator: M-35A

Report to: Joel Ward (Ext 5294, M/S 887A)

Request: LWR 582896

Laboratory log # 04-19-90-32462

Subject: FTIR Analysis of NVR and Filtered Particulate samples from M-52 Spray Booth for the presence of Teflon
Sampled 16 Apr. 1990

FTIR analysis has been carried out on NVR fallout samples and particulate samples from the M-52 spray booth. In particular, each sample was checked for the presence of Teflon residue. The presence of Teflon was determined by the appearance of the C-F absorbance peaks at about 1160 and about 1230 wavenumbers.

Eight fallout NVR samples and eight filter samples (including ref. samples) were received for testing.

No Teflon was detected with any of the samples.


Copies of the FTIR spectra are attached.


R. C. Raisor, Spectrochemical Analysis
LAB90109
B1448

ORIGINAL PAGE IS
OF POOR QUALITY

TWR-50012


O-2



TWR-50012

O-3


NVR SAMPLE #2 SOUTH EAST CORNER, ATR CAST, LWR 582896.002 19 Apr 90 14:33:26



TWR-50012


O-4

NVR SAMPLE #3 EAST SIDE MIDDLE, ATR CAST, LWR 582896.003 19 Apr 90 14:43:54




TWR-50012

0-5



TWR-50012


O-6



TWR-50012

0-7


NVR SAMPLE #6 NORTH EAST CORER, ATR CAST LWR 582896.006 19 Apr 90 19:27:13



TWR-50012


O-8

NVR SAMPLE #7 NORTH WEST CORNER ATR CAST LWR 582896.007 19 Apr 90 19:33:59



TWR-50012


O-9



TWR-50012

O-10


SAMPLE #1 CLAMPED 1ST FREON TF CONTROL LWR 582896.009
19 Apr 90 19:50:18



TWR-50012


O-11

SAMPLE #2 CLAMPED SOUTH EAST CORNER LWR 582896.010 19 Apr 90 19 58.38




TWR-50012

O-12



TWR-50012


O-13



TWR-50012

O-14


SAMPLE #5 CLAMPED SOUTH WEST CORNER LWR 582896.013 19 Apr 90 20:43:04



TWR-50012

O-15


SAMPLE #6 CLAMPED NORTH EAST CORNER LWR 582896.014 19 Apr 90 21 36 19



TWR-50012


O-16

SAMPLE #7 CLAMPED NORTH WEST CORNER LWR 582896.015 F 19 Apr 90 21:44:01



TWR-50012

O-17



TWR-50012
O-18

Appendix P

CTP-0142, Revision B, Conscan Data

REVISION _____

DOC NO. TWR-50012 VOL _____
SEC PAGE P-1

SHOP TRAVELER (CONTINUATION)

TWR-50012
P.2

FORM TC 1794

ORIGINAL PAGE IS
OF POOR QUALITY

26


SHOP TRAVELER (CONTINUATION)

ORIGINAL PAGE IS
OF POOR QUALITY

TWR-50012

P-3

FORM 1C 1794



Appendix Q

CTP-0142, Revision B, Witness Panel Pull Test Data

REVISION _____

DOC NO. TWR-50012 VOL _____
SEC PAGE Q-1

LWR #: CTP-8A
Work Order: HR61A
Originator: V. FITCH

Failure Mode Key
1 = Adhesive/Metal 5 = Cohesive/Rubber 10 = Failure Comment
2 = Cohesive/Adhesive 6 = Adhesive/Rubber TB = Tab Broke
3 = Adhesive/Phenolic 7 = Cohesive/Liner B = Button Side
4 = Cohesive/Phenolic 8 = Adhesive/Liner P = Panel Side
9 = Void IT = Invalid Test

Date: 21MAY90 Test Machine: INSTR4505 Temperature: 70 Deg. F
Technician: J. WARD Test Type: Type III Tensile Crosshead Speed: .05 in/min

Spec No.	Segment ID.	Panel ID.	Dia. (in)	Cross Section	Max Load (lbs)	Max Stress (psi)	Failure Mode Analysis										
							1	2	3	4	5	6	7	8	9	10	
1	CTP-0142	A 0001405	1.12600	0.999	4503	4512	10	50									F
2	CTP-0142	A 0001405	1.12600	0.999	4970	4774			100								
3	CTP-0142	A 0001405	1.12600	0.999	5251	5254			100								
4	CTP-0142	A 0001405	1.12600	0.999	4352	4355			10	50							
5	CTP-0142	A 0001405	1.12600	0.999	4540	4543	10	50									F
6	CTP-0142	A 0001405	1.12600	0.999	4771	4774			100								
7	CTP-0142	A 0001405	1.12600	0.999	5385	5389			100								
8	CTP-0142	A 0001405	1.12600	0.999	5318	5322	5	55									F
9	CTP-0142	A 0001405	1.12600	0.999	2647	2845	60	40									F
10	CTP-0142	A 0001405	1.12600	0.999	4251	4254	20	80									F
11	CTP-0142	A 0001405	1.12600	0.999	5458	5462			100								
12	CTP-0142	A 0001405	1.12600	0.999	4750	4753	10	50									P

Average (FSI): 4748

Standard Deviation: 708.9

Coeff. of Var.: 14.9

Prepared by the Space Contamination Control Laboratory

ORIGINAL PAGE IS
OF POOR QUALITY

TWR-50012
Q-2

LWR #: CTP-0F
Work Order: HR61A
Originator: V. FITCH

Failure Mode Key
1 = Adhesive/Metal
2 = Cohesive/Adhesive
3 = Adhesive/Phenolic
4 = Cohesive/Phenolic
5 = Cohesive/Rubber
6 = Adhesive/Rubber
7 = Cohesive/Liner
8 = Adhesive/Liner
9 = Void
10 = Failure Comment
TB = Tab Broke
B = Button Side
F = Panel Side
IT = Invalid Test

Date: 21MAY90 Test Machine: INSTR4505
Technician: J. WARD Test Type: Type III Tensile

Temperature: 70 Deg. F
Crosshead Speed: .05 in/min

Spec No.	Segment ID.	Panel ID.	Serial	Dia (in)	Section (in ²)	Load (lbs)	Stress (psi)	Failure Mode Analysis									
								1	2	3	4	5	6	7	8	9	10
1	CTP-0142	F 0001582		1.12800	0.999	5669	5672										
2	CTP-0142	F 0001582		1.12800	0.999	5318	5322										
3	CTP-0142	F 0001582		1.12800	0.999	5565	5568										
4	CTP-0142	F 0001582		1.12800	0.999	5464	5468										
5	CTP-0142	F 0001582		1.12800	0.999	5719	5723										
6	CTP-0142	F 0001582		1.12800	0.999	6041	6045										
7	CTP-0142	F 0001582		1.12800	0.999	5881	5884	5	95								
8	CTP-0142	F 0001582		1.12800	0.999	5115	5119	10	98								
9	CTP-0142	F 0001582		1.12800	0.999	5621	5625										
10	CTP-0142	F 0001582		1.12800	0.999	5650	5654										
11	CTP-0142	F 0001582		1.12800	0.999	5717	5721										
12	CTP-0142	F 0001582		1.12800	0.999	5214	5217										
Average (PSI):								5583		1	99						
Standard Deviation:								267.5									
Coeff. of Var:								4.8									

Prepared by the Space Contamination Control Department

ORIGINAL PAGE IS
OF POOR QUALITY

TWR-50012
Q-3

LWR #: CTP-08
Work Order: HR61A
Originator: V. FITCH

Failure Mode Key
1 = Adhesive/Metal 5 = Cohesive/Rubber 10 = Failure Comment
2 = Cohesive/Adhesive 6 = Adhesive/Rubber TB = Tab Broke
3 = Adhesive/Phenolic 7 = Cohesive/Liner B = Button Side
4 = Cohesive/Phenolic 8 = Adhesive/Liner F = Panel Side
9 = Void IT = Invalid Test

Date: 21MAY98 Test Machine: INSTR4505 Temperature: 70 Deg. F
Technician: J. WARD Test Type: Type III Tensile Crosshead Speed: .05 in/min

Spec No.	Segment ID.	Panel ID. Serial	Dia (in)	Section (in2)	Load (lbs)	Max Stress (psi)	Failure Mode Analysis									
							1	2	3	4	5	6	7	8	9	10
1	CTP-0142	B 0000226	1.12800	0.999	5335	5339										
2	CTP-0142	B 0000226	1.12800	0.999	4469	4472	18	80								F
3	CTP-0142	B 0000226	1.12800	0.999	5266	5070										
4	CTP-0142	B 0000226	1.12800	0.999	5154	5157										
5	CTP-0142	B 0000226	1.12800	0.999	5792	5795	18	90								P
6	CTP-0142	B 0000226	1.12800	0.999	5168	5171	18	90								P
7	CTP-0142	B 0000226	1.12800	0.999	5263	5266										F
9	CTP-0142	B 0000226	1.12800	0.999	4863	4866										
9	CTP-0142	B 0000226	1.12800	0.999	4938	4933	18	90								
10	CTP-0142	B 0000226	1.12800	0.999	4292	4295	15	85								F
11	CTP-0142	B 0000226	1.12800	0.999	5076	5102										
12	CTP-0142	B 0000226	1.12800	0.999	5462	5465										

Average (PSI): 5044

Standard Deviation: 753.2

Coeff. of Var: 7.1

ORIGINAL PAGE IS
OF POOR QUALITY

Prepared by the Space Contamination Control Laboratory

TWR-50012
Q-4

LHR #: CTF-06
Work Order: HR61A
Originator: V. FITCH

1 = Adhesive/Metal
2 = Cohesive/Adhesive
3 = Adhesive/Phenolic
4 = Cohesive/Phenolic

Failure Mode Key
5 = Cohesive/Rubber
6 = Adhesive/Rubber
7 = Cohesive/Liner
8 = Adhesive/Liner
9 = Void

10 = Failure Comment
TB = Tab Broke
B = Button Side
P = Panel Side
IT = Invalid Test

Date: 21MAY98
Technician: J. WARD

Test Machine: INSTR4505

Test Type: Type III Tensile

Temperature: 70 Deg. F
Crosshead Speed: .05 in/min

Spec No.	Segment ID.	Panel ID... Serial	Dia (in)	Section (in ²)	Load (lbs)	Stress (psi)	Failure Mode Analysis								
							1	2	3	4	5	6	7	8	
1	CTF-0142	G 0000834	1.12000	0.999	4178	4181	10	92							P
2	CTF-0142	G 0000834	1.12000	0.999	4128	4183	30	70							F
3	CTF-0142	G 0000834	1.12000	0.999	4645	4648	15	65							P
4	CTF-0142	G 0000834	1.12002	0.999	5326	5329		100							
5	CTF-0142	G 0000834	1.12000	0.999	4781	4785	10	98							F
6	CTF-0142	G 0000834	1.12000	0.999	6603	6607		100							
7	CTF-0142	G 0000834	1.12000	0.999	5743	5747		100							
8	CTF-0142	G 0000834	1.12000	0.999	5965	5969		100							
9	CTF-0142	G 0000834	1.12000	0.999	5128	5132		100							
10	CTF-0142	G 0000834	1.12000	0.999	5624	5627	5	95							P
11	CTF-0142	G 0000834	1.12000	0.999	5484	5488		100							
12	CTF-0142	G 0000834	1.12000	0.999	5889	5893		100							
Average (FSI):							5242		6	94					
Standard Deviation:							674.6								
Coeff. of Var:							12.9								

Prepared by the Space Contamination Control Laboratory

TWR-50012

Q-5

ORIGINAL PAGE IS
OF POOR QUALITY

LWR #: CTP-BC
Work Order: HR61A
Originator: V. FITCH

Failure Mode Key
1 = Adhesive/Metal 5 = Cohesive/Rubber 10 = Failure Comment
2 = Cohesive/Adhesive 6 = Adhesive/Rubber TB = Tab Broke
3 = Adhesive/Phenolic 7 = Cohesive/Liner B = Button Side
4 = Cohesive/Phenolic 8 = Adhesive/Liner P = Panel Side
9 = Void IT = Invalid Test

Date: 21MAY90 Test Machine: INSTR4505
Technician: J. WARD Test Type: Type III Tensile Temperature: 78 Deg. F
Crosshead Speed: .85 in/min

Spec No.	Segment ID	Panel ID, Serial	Dia (in)	Section (in2)	Load (lbs)	Max Stress (psi)	Failure Mode Analysis									
							1	2	3	4	5	6	7	8	9	10
1	CTP-0142	C 0000081	1.12800	0.999	4498	4501	10	90								P
2	CTF-0142	C 0000081	1.12800	0.999	4355	4358	20	80								P
3	CTP-0142	C 0000081	1.12800	0.999	4232	4235	20	80								F
4	CTP-0142	C 0000091	1.12800	0.999	4129	4132	25	75								F
5	CTP-0142	C 0000081	1.12800	0.999	4084	4087	10	90								P
6	CTF-0142	C 0000081	1.12800	0.999	5026	5039	10	90								P
7	CTP-0142	C 0000091	1.12800	0.999	5484	5488		100								
8	CTP-0142	C 0000081	1.12800	0.999	4447	4450	15	85								P
9	CTP-0142	C 0000081	1.12800	0.999	5184	5187	10	90								P
10	CTP-0142	C 0000081	1.12800	0.999	5533	5537	10	90								F
11	CTP-0142	C 0000081	1.12800	0.999	5141	5144	10	90								P
12	CTF-0142	C 0000081	1.12800	0.999	4666	4669	10	90								P

Average (PSI): 4800
Standard Deviations: 479.3
Coeff. of Var: 16.0

ORIGINAL PAGE IS
OF POOR QUALITY

LWR # :	CTP-BH	1 = Adhesive/Metal	Failure Mode Key
Work Order:	HR61A	2 = Cohesive/Rubber	10 = Failure Comment
Originator:	V. FITCH	3 = Adhesive/Adhesive	TB = Tab Broke
		4 = Adhesive/Phenolic	B = Button Side
		5 = Cohesive/Phenolic	F = Panel Side
		6 = Adhesive/Rubber	
		7 = Cohesive/Liner	
		8 = Adhesive/Liner	
		9 = Void	IT = Invalid Test

Date: 21MAY98 Test Machine: INSTR4505 Temperature: 70 Deg. F
 Technician: J. WARD Test Type: Type III Tensile Crosshead Speed: .05 in/min

Spec No.	Segment ID.	Panel ID.	Panel Serial	Dia (in)	Section (in ²)	Load (lbs)	Stress (psi)	Failure Mode Analysis										
								1	2	3	4	5	6	7	8	9	10	
1	CTP-B142	H 0001471		1.12800	0.999	5451	5455											
2	CTP-B142	H 0001471		1.12800	0.999	5180	5184											
3	CTP-B142	H 0001471		1.12800	0.999	5003	5007	10	90								P	
4	CTP-B142	H 0001471		1.12800	0.999	5692	5696											
5	CTP-B142	H 0001471		1.12800	0.999	4950	4954	10	90								P	
6	CTP-B142	H 0001471		1.12800	0.999	5690	5694											
7	CTP-B142	H 0001471		1.12800	0.999	5966	5970											
8	CTP-B142	H 0001471		1.12800	0.999	5411	5415	5	95								B	
9	CTP-B142	H 0001471		1.12800	0.999	3866	3869	45	55								P	
10	CTP-B142	H 0001471		1.12800	0.999	5848	5852	5	95								B	
11	CTP-B142	H 0001471		1.12800	0.999	5961	5965											
12	CTP-B142	H 0001471		1.12800	0.999	4861	4864	5	95								P	
Average (PSI):								5327		7	93							
Standard Deviation:								602.6										
Coeff. of Var:								11.3										

Prepared by the Space Contamination Control Laboratory

TWR-50012

ORIGINAL PAGE IS
OF POOR QUALITY

Q-7

LWR #: CTP-0D
Work Order: H03HB
Originator: V. FITCH

Failure Mode Key
1 = Adhesive/Metal 5 = Cohesive/Rubber 10 = Failure Comment
2 = Cohesive/Adhesive 6 = Adhesive/Rubber TB = Tab Broke
3 = Adhesive/Phenolic 7 = Cohesive/Liner B = Button Side
4 = Cohesive/Phenolic 8 = Adhesive/Liner P = Panel Side
9 = Void II = Invalid Test

Date: 21MAY98 Test Machine: INSTRN4505 Temperature: 70 Deg. F
Technician: V.WARNER Test Type: Type III Tensile Crosshead Speed: .05 in/min

Spec No.	Segment ID	Panel ID	Dia (in)	Section (in ²)	Load (lbs)	Max Stress (psil)	Failure Mode Analysis										
							1	2	3	4	5	6	7	8	9	10	
1	CTP-0142	D 0001280	1.12800	8.999	4335	4338	10	90									
2	CTP-0142	D 0001280	1.12800	8.999	5388	5391	5	95									P
3	CTP-0142	D 0001280	1.12800	8.999	4302	4305	10	90									P
4	CTP-0142	D 0001280	1.12800	8.999	5085	5088		100									P
5	CTP-0142	D 0001280	1.12800	8.999	5421	5425		100									
6	CTP-0142	D 0001280	1.12800	8.999	5468	5472		100									
7	CTP-0142	D 0001280	1.12800	8.999	4285	4288	10	90									P
8	CTP-0142	D 0001280	1.12800	8.999	5378	5374		100									
9	CTP-0142	D 0001280	1.12800	8.999	5825	5829		100									
10	CTP-0142	D 0001280	1.12800	8.999	4342	4345	10	90									P
11	CTP-0142	D 0001280	1.12800	8.999	5403	5406		100									P
12	CTP-0142	D 0001280	1.12800	8.999	4986	4989	5	95									P
Average (PSI):						5888	4	96									
Standard Deviations:						557.2											
Coeff. of Var:						11.1											

LWR #:	CTP-01	Failure Mode Key
Work Order:	HR61A	1 = Adhesive/Metal 5 = Cohesive/Rubber
Originator:	V. FITCH	2 = Cohesive/Adhesive 6 = Adhesive/Rubber
		3 = Adhesive/Phenolic 7 = Cohesive/Liner
		4 = Cohesive/Phenolic 8 = Adhesive/Liner
		9 = Void
		10 = Failure Comment
		TB = Tab Broke
		B = Button Side
		P = Panel Side
		IT = Invalid Test

Date: 21MAY98 Test Machine: INSTR4505 Temperature: 70 Deg. F
 Technician: J. HARD Test Type: Type III Tensile Crosshead Speed: .05 in/min

Spec No.	Segment ID:	Panel ID: Serial	Dia (in)	Section (in2)	Load (lbs)	Max Stress (psi)	Failure Mode Analysis									
							1	2	3	4	5	6	7	8	9	10
1	CTP-0142	I 0001238	1.12800	0.999	5233	5236	5	95								P
2	CTP-0142	I 0001238	1.12800	0.999	5373	5377		100								
3	CTP-0142	I 0001238	1.12800	0.999	4423	4431	10	90								F
4	CTP-0142	I 0001238	1.12800	0.999	5768	5791	5	95								F
5	CTP-0142	I 0001238	1.12800	0.999	5564	5567		100								
6	CTP-0142	I 0001238	1.12800	0.999	5212	5215		100								P
7	CTP-0142	I 0001238	1.12800	0.999	4426	4429	20	80								
8	CTP-0142	I 0001238	1.12800	0.999	5166	5178		100								
9	CTP-0142	I 0001238	1.12800	0.999	4873	4877	5	95								F
10	CTP-0142	I 0001238	1.12800	0.999	4261	4263	10	90								F
11	CTP-0142	I 0001238	1.12800	0.999	4643	4646	5	95								P
12	CTP-0142	I 0001238	1.12800	0.999	5377	5380	5	95								P
Average (PSI):							4999		5	95						
Standard Deviation:								521.2								
Coeff. of Var:									10.4							

Printed by the Space Contamination Control Laboratory

TWR-50012

Q-9

ORIGINAL PAGE IS
OF POOR QUALITY

Failure Mode Key:
 1 = Adhesive/Metal 5 = Cohesive/Rubber 10 = Failure Comment
 2 = Cohesive/Adhesive 6 = Adhesive/Rubber TB = Tab Broke
 3 = Adhesive/Phenolic 7 = Cohesive/Liner B = Button Side
 4 = Cohesive/Phenolic 8 = Adhesive/Liner P = Panel Side
 9 = Void IT = Invalid Test

Date: 21MAY98 Test Machine: INSTR4585 Temperature: 70 Deg. F
 Technician: J. WARD Test Type: Type III Tensile Crosshead Speed: .05 in/in

Specimen No.	Segment ID	Panel	Dia	Section	Load (lb)	Cross Stress (in ⁻²)	Failure Mode Analysis							
							1	2	3	4	5	6	7	8
1	CTP-0142	E 0881263	.12800	0.999	4888	4883		5	95					P
2	CTP-0142	E 0881263	.12800	0.999	4874	4877		5	95					P
3	CTP-0142	E 0881263	.12800	0.999	4918	4922		5	95					P
4	CTP-0142	E 0881263	.12800	0.999	4984	4987			100					P
5	CTP-0142	E 0881263	.12800	0.999	5224	5228			100					P
6	CTP-0142	E 0881263	.12800	0.999	5174	5178			100					P
7	CTP-0142	E 0881263	.12800	0.999	4769	4772		5	95					P
8	CTP-0142	E 0881263	.12800	0.999	5046	5050			100					P
9	CTP-0142	E 0881263	.12800	0.999	5248	5243			100					P
10	CTP-0142	E 0881263	.12800	0.999	4925	4929		10	90					P
11	CTP-0142	E 0881263	.12800	0.999	5861	5864		5	95					P
12	CTP-0142	E 0881263	.12800	0.999	4477	4480		10	90					P
Average (psi)							4954	4	96					
Standard Deviation							217.5							
Coefficient of Variation							4.3							

ORIGINAL PAGE IS
OF POOR QUALITY

LWR #: CTP-8J
Work Order: HR61A
Originator: V. FITCH

Failure Mode Key
1 = Adhesive/Metal 5 = Cohesive/Rubber
2 = Cohesive/Adhesive 6 = Adhesive/Rubber
3 = Adhesive/Phenolic 7 = Cohesive/Liner
4 = Cohesive/Phenolic 8 = Adhesive/Liner
9 = Void 10 = Failure Comment
 TB = Tab Broke
 B = Button Side
 P = Panel Side
 IT = Invalid Test

Dates: 21MAY98 Test Machine: INSTR4305 Temperature: 70 Deg. F
Technician: J. WARD Test Type: Type III Tensile Crosshead Speed: .05 in/min

Spec No.	Segment ID:	Panel ID, - Serial	Dia (in)	Section (in ²)	Load (lbs)	Max Stress (psi)	Failure Mode Analysis									
							1	2	3	4	5	6	7	8	9	10
1	CTP-0142	J 0001257	1.12800	0.999	4098	4100	15	85								P
2	CTP-0142	J 0001257	1.12800	0.999	5515	5518		100								
3	CTP-0142	J 0001257	1.12800	0.999	5642	5646		100								
4	CTP-0142	J 0001257	1.12800	0.999	5815	5822	5	95								F
5	CTP-0142	J 0001257	1.12800	0.999	4366	4369	15	85								F
6	CTP-0142	J 0001257	1.12800	0.999	5120	5124		100								P
7	CTP-0142	J 0001257	1.12800	0.999	5588	5592	5	95								P
8	CTP-0142	J 0001257	1.12800	0.999	4696	4699	10	90								P
9	CTP-0142	J 0001257	1.12800	0.999	4929	4932	10	90								P
10	CTP-0142	J 0001257	1.12800	0.999	5820	5824		100								
11	CTP-0142	J 0001257	1.12800	0.999	4897	4901		100								
12	CTP-0142	J 0001257	1.12800	0.999	5518	5518		100								
Average (PSI):							5103	5	95							
Standard Deviation:							537.3									
Coeff. of Var:							10.5									

THIS PAGE IS
OF POOR QUALITY



Appendix R

Pass/Fail Criteria

REVISION _____

DOC NO. TWR-50012 VOL _____
SEC PAGE _____
R-1

Thiokol CORPORATION
SPACE OPERATIONS

6 June 1990
L713-FY90-M403

TO: Distribution

FROM: L. J. Manuel
Test Planning and Reports

SUBJECT: Update of Pass/fail Criteria for the M-52 Spray Booth Qualification

REFERENCE: Test Readiness Review Package, Titled "CTR-0142 Rev B, Qualification Test for Process Change Moving the Aft and Fwd Dome Painting and Adhesives Application Location from the Bottom of the Paint Pits to the M-52 Spray Booth".

The pass/fail criteria for the steel/epoxy/steel test portion of the M-52 spray booth qualification has been revised. The pass/fail criteria was:

B. Steel-Epoxy Bonds - If the exposed panel set (5 total) has significantly less bond strength at the 95% confidence level than the control panel set (5 total) then the test failed.

The revised pass/fail criteria is as follows:

Pass: If the exposed panels averages are above the systems tunnel witness panel database A-basis lower limit, or, if the exposed panel set does not have a significantly lower tensile adhesion bond strength than the control panels at the 95% confidence level.

Fail: If any of the exposed panel averages fall below the systems tunnel witness panel database A-basis lower limit, and, the exposed panel set has a significantly lower tensile adhesion bond strength than the control panels at the 95% confidence level.

The justification for this change is outlined in the attached presentation.

P.O. Box 102, Brigham City, UT 84302-0102 (800) 961-5477

A023243a

Thiokol CORPORATION
SPACE OPERATIONS

TRR Board Concurrence

FOR

R. Eanes
Space Division Sr. V.P.

Frank B. Weller
Space Engineering

W. Watson
SR & QA

G. C. Allard
RSRM Program Management

Roy A. Brink
Operations

Frank Mirel
Board Secretary

Mervy Dan EES4
MSFC Representative

A023243a

REVISION _____

DOC NO. **TWR-50012** VOL _____
SEC PAGE _____
R-3

DISTRIBUTION

S. Kulkarni	L00
C. Speak	E60
R. Davis	A30
R. Bontempo	600
R. Lund	200
R. Bowman	800
D. Brown	560
N. Black	L71
L. Manuel	L71
L. Lott	K68
G. Alford	E60
B. McQuivey	L72
B. Jurewicz	L70
S. Foth	824
R. Plowman	824
B. Anderson	650
V. Fitch	L62B
S. Mildenhall	E80
R. Clark	654
D. Earl	692
A. Braxton	K68
B. Meyer	K68
C. Jensen	L72
S. Moake	692
D. Call	692
K. Wilks	E63
R. Furrows	L72
J. Sutton	L72

**M-52 SPRAY BOOTH QUALIFICATION
CTP-0142, REVISION B
TENSILE ADHESION TESTS**

**Scott D. Mildenhall
Materials and Process**

**Vern Fitch
Thermal Insulation Design**

1 June 1990

Thiokol CORPORATION
SPACE OPERATIONS

INFORMATION ON THIS PAGE WAS PREPARED TO SUPPORT AN ORAL PRESENTATION
AND CANNOT BE CONSIDERED COMPLETE WITHOUT THE ORAL DISCUSSION

M-52 SPRAY BOOTH QUALIFICATION TENSILE TESTS
Background

- CTP-0142, Revision B was written to include revised witness panel tensile adhesion test
- Two sets of five panels (12 buttons on each panel) were tested
 - One control set of five panels covered with craft paper
 - One set of five panels exposed in the M-52 spray booth
- The tests were run per the planning and did not meet the pass/fail criteria set up during the TRR.
- The exposed panel set will not have a significantly lower tensile adhesion bond strength than the control panels at the 95% confidence level

M-52 SPRAY BOOTH QUALIFICATION TENSILE TESTS
Objective

- Show that the results of the tensile tests are technically acceptable based on the high tensile strengths obtained and how the data compares with the systems tunnel witness panel database

- Show how the tightness of the test data (low panel to panel variation) affected the calculations used to demonstrate compliance to the requirements at a 95% confidence level

M-52 SPRAY BOOTH QUALIFICATION TENSILE TESTS
Discussion

■ Statistical Equation

$$t = \sqrt{\frac{\bar{X}_c - \bar{X}_e}{\frac{(S_c)^2}{n_c} + \frac{(S_e)^2}{n_e}}}$$

"t" = is based on the confidence level required and based on the number of samples to be tested (obtained from statistical tables)

"X" = the mean value for the data

"S" = the standard deviation of the data

"c" = control panel sets

"e" = exposed panel sets

- "t" for a 95% confidence level and 5 samples per set equals 1.86
 - Calculated higher values of "t" indicate that the requirement at a 95% confidence level has not been met
 - Calculated "t" for the two data sets was 2.936, indicating that there was a statistical difference between the two data sets at a 95% confidence level

M-52 SPRAY BOOTH QUALIFICATION TENSILE TESTS
Discussion (Cont.)

Why the data showed a statistical difference

- There was a slight difference in the bond strengths of the two sets of panels
 - The exact physical cause of this difference is not known
- The panel to panel standard deviations were very small for these two data sets in comparison to the systems tunnel witness panels
 - Control set panel to panel standard deviation was 224 psi (cv 4.3%)
 - Exposed set panel to panel standard deviation was 130 psi (cv 2.7%)
 - System tunnel witness panel to panel standard deviation is 486 psi (cv 8.5%)
- This is near the anticipated coefficient of variation of the data used in determining the pass/fail criteria
- Recalculating "t" using the CV from the systems tunnel witness panel database (8.5%) produces an acceptable condition, $t = 1.24$
- The exposed panels and control panels were tightly controlled and produced unexpectedly low bond strength variations from panel to panel
- The statistical pass/fail criteria was not met because we underestimated the discriminatory capability of the test

M-52 SPRAY BOOTH QUALIFICATION TENSILE TESTS
Discussion (Cont.)

EXPOSED <u>PANEL SET</u>		TENSILE <u>ADHESION</u> (psi)	STANDARD <u>DEVIATION</u> (psi)	COEFFICIENT <u>OF VARIATION</u> (percent)	ADHESIVE <u>PERCENT</u>	FAILURE MODE <u>COHESIVE</u> (Percent)
PANEL A	4748	709		14.9	10	90
PANEL B	5044	359		7.1	5	95
PANEL C	4800	479		10	13	88
PANEL D	5008	557		11.1	4	96
PANEL E	4954	218		4.4	4	96
AVERAGE	4911	130*		2.7*	7.2	93
CONTROL <u>PANEL SET</u>						
PANEL F	5583	268		4.8	1	99
PANEL G	5242	675		12.9	6	94
PANEL H	5327	603		11.3	7	93
PANEL I	4999	521		10.4	5	95
PANEL J	5103	537		10.5	5	95
AVERAGE	5251	224*		4.3*	4.8	95.2
SYSTEMS TUNNEL <u>WITNESS PANELS</u>						
AVERAGE	5733	486*		8.5*	0	100
A-BASIS LOWER LIMIT	4412					


* Standard deviation (or coefficient of variation) of the panel averages.

M-52 SPRAY BOOTH QUALIFICATION TENSILE TESTS
Discussion (Cont.)

Why the data indicates an acceptable condition

- The individual panel average tensile strength values obtained for both the control set (4999, 5103, 5242, 5327, 5583 psi) and the exposed set (4748, 4800, 4964, 5008, 5055 psi) exceed the lower A-basis limits (4412 psi) of the closest comparable database (systems tunnel witness panels)
- This database was earlier discounted for comparison
 - It was felt that the silane primer adhesion promoter would greatly bias the database by increasing bond strength
- Lab studies have shown that the cleaner a bond surface is the less the improvement in bond strength can be obtained with the use of silane primer
- The control and exposed test panel sets exhibited excellent cleanliness and as a result the bond strengths, without silane primer, were very good

RSRM SYSTEMS TUNNEL WITNESS PANELS
TYPE III (IIC PANELS) <STEEL/EPOXY/STEEL>
 with A-basis lower limit



TWR-50012

R-12

Prepared by SPACE MAP
 24-MAY-90
 FSTSTUN3.DRW

M-52 SPRAY BOOTH QUALIFICATION TENSILE TESTS

Summary/Conclusion

Summary

- The pass/fail criteria was not met because the discriminatory capability of the test was underestimated
- The individual average tensile strength values for the exposed panels all exceed the A-basis lower limit of the systems tunnel witness panel database

Conclusions

- The results of the witness panel tensile tests conducted per CTP-0142 Revision B are technically acceptable
- The total data package accumulated per CTP-0142 Revision A and CTP-0142 Revision B verify that the M-52 spray booth is acceptable for spraying domes

M-52 SPRAY BOOTH QUALIFICATION TENSILE ADHESION TESTS
Recommendations

- Write a memo which documents the proposed changes to the pass/fail criteria established in the TRR. (CTP-0142, Revision B)
 - All TRR board members will sign-off on this memo, documenting their acceptance of the changes to the pass/fail criteria.
- Pass/Fail Criteria

Pass:

If the exposed panels averages are above the systems tunnel witness panel database A-basis lower limit,

- or -

If the exposed panel set does not have a significantly lower tensile adhesion bond strength than the control panels at the 95% confidence level.

Fail:

If any of the exposed panel averages fall below the systems tunnel witness panel database A-basis lower limit,

- and -

The exposed panel set has a significantly lower tensile adhesion bond strength than the control panels at the 95% confidence level.

- Certify the M-52 spray booth acceptable for spraying forward and aft domes based on the testing conducted per CTP-0142 Revision A, CTP-0142 Revision B, and based on the TRR board memo.

DISTRIBUTION

<u>Recipient</u>	<u>No. of Copies</u>	<u>Mail Stop</u>
Print Crib	5	Q51B1
R. Papasian	40	E62A
N. Black	1	L71
L. Manuel	2	L71
F. Miller	3	L72B
B. Howard	3	337A
R. Furrows	1	L72
K. Wilks	1	E63
J. Seiler	1	L72
S. Marsh	1	E63
J. Jeppsen	1	693
L. Siedner	1	693
V. Fitch	1	L62
F. Baugh	1	L62
T. Lewis	1	565
P. Petty	1	L10
D. Call	1	692
K. Lowry	1	695
R. Marrs	1	L90
C. Herrick	1	887A
C. Whitworth	1	L90
S. Mildenhall	1	L90
D. Earl	1	692
Data Management	5	L72B

